



UNIVERSITY OF CALCUTTA
OFFICE OF THE UNIVERSITY ENGINEER
87/1, College Street
Darbhanga Building, Ground Floor
Kolkata-700073
Website :-www.caluniv.ac.in

NOTICE INVITING QUOTATION

University of Calcutta invites **sealed** tender from resourceful and bonafide contractors for the following work

1.	N.I.Q. No:	Eng /ET-93/21-22 Date: 01.10.2021
2.	Name of the work:	<u>Repairing of existing defunct A.C machines&annual maintenance of all the A.C machines as mentioned below(annexture 1&2d)in the department of applied optonics& photonics & A.K.Chowdhury school of I.T in tower I,Technology campus,Salt lake under University of Calcutta..</u>
3.	Estimated Cost put to Tender:	N.A.
4.	Earnest Money:	A sum of 5% of the quoted amount in the form of CTS demand draft in favour of University of Calcutta payable at Kolkata is to be attached with the Tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenders on application after issuing of work order to the successful bidder. In case of successful tender the EMD will be returned on application after an equal amount of security deposit is ducted by the University from the running bills. EMD is not exempted in any case.
5.	Time of completion:	12months
6.	Eligibility Criteria and Documents to be submitted along with Application.	Valid trade License , GST & PAN and credential for satisfactory completion of similar nature of job amounting75 % of the estimated value in a single tender in the last three financial years in Government /Government Undertaking or University of Calcutta.Original documents may be asked for verification of technical checking on the date of issuing tender paper . Failing to produce original documents, the tender will be rejected. The participant bidder must submit the following documents in sealed envelope in the tender box kept at the Office of the Engineer at the Ground Floor of the Darbhanga Building, University of Calcutta, 87/1, College Street, Kolkata – 700073 within the last date of submission of the tender. <ol style="list-style-type: none">1. NIT documents duly filled and signed by the intending bidder.2. Bank Draft for EMD in favour of the University of Calcutta.3. Self-attested copy of Valid trade License , GST & Pan and credentials for satisfactory completion of similar nature of jobs under Government, Government Undertaking and Universities etc. within last three years.4. Application through postal service or courier service is not accepted.5. Bidders are requested to visit the site & check the machines physically before submitting their quotations.
7.	Date of receipt of application for tender	On 08.10.2021 from 11 am to 4 pm (Must contain above mentioned. Documents. The application duly signed by Engineer CU should be enclosed with tender documents
8.	Date of issue of tender papers	TO BE DOWNLOADED FROM WEBSITE.(www. caluniv.ac.in)
9.	Last Date and Time of tender Submission	Dully filled and signed tender/quotation to be submitted on 25/ 10/ 2021 from 11am to 2.00 PM in to the Tender Box kept in the Office of the University Engineer
10.	Date and Time of Tender Opening	At or after 3pm 25/ 10/ 2021 at the Office of the University Engineer. Intending bidders are requested to be present at the time of opening tenders/quotations.

N.I.T no :Name of work and the date of opening should be written on the sealed envelope otherwise tender will not be opened and will be rejected.

The undersigned reserves the right to reject any or all Tenders without assigning any reason what so ever.



UNIVERSITY OF CALCUTTA

Name of the work:- Repairing of existing defunct A.C machines&annual maintenance of all the A.C machines as mentioned below(annexture 1&2d) in the department of applied optonics& photonics & A.K.Chowdhury school of I.T in tower I,Technology campus,Salt lake under University of Calcutta..

N. I.Q. no- Eng /ET-93/21-22 Date: 01.10.2021

Estimated cost Put to Tender:-N.A.

Name of Agency:-

Address of Agency:-

Rate quoted by Agency:- (in figure and words)

Signature of the Agency with date &stamp:-



UNIVERSITY OF CALCUTTA

N. I.Q. no : Eng /ET-93/21-22 Date: 01.10.2021

Item Rate contract

GENERAL TERMS AND CONDITION

1. Eligible Tenders will have to download the tender papers from the website & drop the filled tender papers signed with seal and date at every page along with copy of Valid Trade license's, GST & PAN and Credential for satisfactory completion of similar nature of job amounting to at least seventy five percent of the job value in a single tender from any Government, Govt. undertaking or University of Calcutta in the last three financial year in sealed envelope in the Tender box kept in the Office of the undersigned with in the specified time mentioned in the NIT which will be opened by the undersigned or by his representative with in **the specified time and date mentioned in the NIT** The tendered must write the name of the work , NIT no , the date of opening and name of the bidder on the envelop failing which the tender will not be opened thus will be treated as cancelled.
2. The rate should be quoted after inspection of the site and inclusive of all incidental charges i.e. freight, insurances, labour insurances, handling charges, necessary government taxes, duties etc as well as the Water, Electricity charges which are to be paid as per rules .
3. The contractor shall be responsible to ensure compliance with the provision of minimum wages act 1948 as modified up to date and the rules made in respect of any employees, employed by the contractor directly or through the petty or subcontractor for the purpose of carrying this contract. The contractor shall be responsible for any damage, injury or loss caused by the work or workmen to any person, animal or material during the progress of work.
4. Liquidated damage will be charged to the contractor if they fail to complete the work within the stipulated time, 0.01% per day to a maximum limit of 10 % of the contract value .



5. The allotted time for completion of the work as specified in the NIT from the date of receipt of work order .Time is the essence of this contract. Normally no time extension will be granted. In case of prayer for extension of time the University authority has the full right reserved to grant it or discard it.

6. (a) If the successful contractor's bid rate is 80% or less than the estimated amount put to tender the contractor will have to submit a Bank Guarantee amounting to 10% of the Tendered amount before issue of Work order failing which the EMD will be forfeited and the agency may be blacklisted. The Bank Guarantee should be valid till the end of the contract period and shall be renewed accordingly if required. This bank Guarantee is an Additional Performance Security .So provision of deducting Security deposit from bills will hold goods per relevant clause of the contract. The bank Gurrantee shall be returned immediately on successful completion of contract.

(b) The University authority will retain a sum amounting to 10% of the bill of the contract for a period of six months from the date of completion of work as **Security Deposit**. Which will be released after a period of six months from the date of completion of the work on application.

7. A sum of 5% of the quoted amount in the form of CTS demand draft in favour of University of Calcutta payable at Kolkata is to be attached with the Tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenders on application after issuing of work order to the successful bidder. In case of successful tender the EMD will be returned on application after an equal amount of security deposit is ducted by the University from the running bills. EMD is not exempted in any case. The earnest money will be returned to unsuccessful tenderers on application after issue of work order to the successful bidder for successful tenderer the EMD will be returned on application after an equal amount of security deposit is deducted from the running bills.

Amount:-Rs

D.D No..... Dated / /20

Name of Issuing Bank:--

Branch :-

8. Work is to be carried out as per specification laid in the B.O.Q or PWD specification as per instruction of the University Engineer or his representative.



9. The materials brought to site for execution of the work should by no means be taken out of site without the permission of the Engineer C.U.

10. The rates must be quoted in words in figure otherwise the tender will be cancelled.

11. The University will not be bound to accept the lowest bidder.

12. The University will not supply any materials to the contractor.

13. The contractor will work under the strict supervision of the Engineer/ Sub-Assistant Engineer. The estimate given along with the tender are provisional payment will be made on the actual work done jointly measured by the Engineer or his representative (Sub-Assistant- Engineer) & the contractor or his representative. The contractor will have to submit bill in printed format in duplicate.

14. The contractor will have to take necessary instruction from the Engineer CU/ Sub-Assistant Engineer regarding the execution of work.

15. Defect & liability Period:- The defect & liability period will be for a period of six months from the date of completion of the job. Any defects pointed out during this period has to be mend good by the agency at their own cost failing which the retention money will be forfeited.

Sd/-

University Engineer

Name of the Agency:

Address :-

Signature of the Agency with date & stamp:-

QUOTATION FOR REPAIRING OF THE EXISTING DEFUNCT A.C MACHINES & ANNUAL MAINTENANCE OF ALL THE A.C MACHINES IN THE DEPARTMENT OF APPLIED OPTONICS & PHOTONICS& DEPARTMENT OF A.K CHOWDHURY SCHOOL OF I.T ,TOWER- I ,TECHNOLOGY CAMPUS,SALT LAKE,UNDER UNIVERSITY OF CALCUTTA.					
Sl.No.	Description of work	Unit	Rate	Quantity	Amount
1	Comprehensive repairing of all existing defunct AC machines incl.supplying & fixing all necy items required for repairing such as running capacitors,blower,gas charging,circuit panel etc.[Quantity of machines are attached in annexure 1 & 2]	item			
2	Comprehensive A.M.C for all the mentioned A.C Machines (Annexure1) in all respect incl.supplying & Fixing necessary items,such as compressor,gas charging,capacitor etc.	item			
(A) TOTAL BASIC COST :(Excluding G.S.T) B)G.S.T EXTRA ON TOTAL TENTATIVE BASIC COST(A)as applicable					

ANNEXTURE 1 (A.K.Chowdhury school of I,T)

DETAILS FOR AIR CONDITION MACHINE

NO	LOCATIO N	QTY	REMARKS
1	410	2 NOS	NEED GAS CHARGE
2	422	2 NOS	NEED GAS CHARGE
3	421	1 NO	Aluminium Coil leakage
4	424	4 NOS	NEED GAS CHARGE
5	416	6 NOS	4 NOS AC GAS CHARG , 1 NO AC FAN MOTOR REPAIR AND 2 NOS AC RE INSTALLATION
6	411	2 NOS	FAN BLADE CHANGE
7	414	1 NO	NEED GAS
8	406	3 NOS	2 NOS AC GAS SHORT 1 NO AC NEED FAN CAPACITOR
9	409	8 NOS AC	ALL AC ALLUMINIUM COIL NEED GAS CHARGE AND 20 FEET COPPER PIPE
10	418	2 NOS	NEED GAS CHARGE
11	419	2 NOS	NEED GAS CHARGE
12	415	2 NOS	NEED GAS CHARGE AND RE INSTALLATION
13	413	1 NO	NEED GAS AND 6 FEET COPPER PIPE
14		2 nos Tower AC	Tower 1 no circuit defect
15	412	2 nos	New

No	Location	Particulars	Report
1	Room No- 326	Voltas 1.5 ton Split	Machine Running Ok, Needs Servicing
2	Room No - 323	Hitachi 2.0 Ton Split	Indoor Unit Open
3	Room No- 328	Voltas 1.5 ton Split	Machine Running Ok, Needs Servicing
4	Room No- 327	Hitachi 2.0 Ton Split	Gas Leakage, Pipe Line Missing, Need 18 feet 5/8 & 1/4, Copper Pipe Line With Insulation & Flair Nut.
5	Room No -329	Hitachi 2.0 Ton Split	Machine Running Ok, Needs Servicing
6	Room No -329	Hitachi 2.0 Ton Split	Machine Running Ok, Needs Servicing
7	Room No -329	Hitachi 2.0 Ton Split	Machine Running Ok, Needs Servicing
8	Room No- 331	Hitachi 2.0 Ton Split	Gas Leakage ,Pipe Line Missing, Need 15 feet 5/8 & 1/4 15 Feet with insulation & Flair Nut.
9	Room No- 331	Hitachi 2.0 Ton Split	Gas Leakage ,Pipe Line Missing, Need 15 feet 5/8 & 1/4 15 Feet with insulation & Flair Nut.
10	Room No- 331	Hitachi 2.0 Ton Split	Gas Leakage ,Pipe Line Missing, Need 15 feet 5/8 & 1/4 15 Feet with insulation & Flair Nut.
11	Room No- 333	Voltas 1.5 ton Split	Machine does not check due to power supply failed.
12	Room No-319	Voltas 2.0 ton Split	Gas Leakage, Pipe Line Damage, Need 12 feet 5/8 & 1/4 Pipe Line With Insulation & Flair Nut
13	Room No-319	Voltas 2.0 ton Split	Gas Leakage, Pipe Line Damage, Need 12 feet 5/8 & 1/4 Pipe Line With Insulation & Flair Nut
14	Room No-334	Voltas 1.5 ton Split	Idu Problem, Error Code- F6
15	Room No-334	Voltas 1.5 ton Split	Gas Short ,B.P.30psig
16	Room No-320	Voltas 1.5 ton Split	Machine not ok ,Outdoor Wire Cutting. Need 3 feet Cable.
17	Room No-330	Hitachi 2.0 Ton Split	Gas Leakage ,Pipe Line Missing, Need 15 feet 5/8 & 1/4 15 Feet with insulation & Flair Nut
18	Room No-330	Hitachi 2.0 Ton Split	Gas Leakage ,Pipe Line Missing, Need 15 feet 5/8 & 1/4 15 Feet with insulation & Flair Nut
19	Room No -322	Voltas 1.5 ton Split	Machine Running Ok. Need Service
20	Room No- 325	Hitachi 2.0 Ton Split	Gas Leakage
21	Room No- 324	Voltas 1.5 ton Split	Machine does not check due to power supply failed
22	Room No- 321	Voltas 1.5 ton Split	ODU Unit Open Out, Pipe Line missing, Need 1/2 & 1/4 With Insulation & Flair Nut.
23	Room No-336	Window	Machine Ok. But Body Damage
24	Room No- 317	Voltas 2.0 ton Split	IDU Open Out ,Gas Leakage, 5/8 & 3/8 Copper Pipe 5 feet Required with Pipe Line & Flair Nut.
25	Room No- 317	Voltas 2.0 ton Split	IDU Open Out ,Gas Leakage, 5/8 & 3/8 Copper Pipe 5 feet Required with Pipe Line & Flair Nut.
26	Room No- 317	Voltas 2.0 ton Split	IDU Open Out ,Gas Leakage, 5/8 & 3/8 Copper Pipe 5 feet Required with Pipe Line & Flair Nut.Outdoor top Cover missing ,Outdoor Motor Defective, Relay ,Capacitor Required
27	Room No -318	Hitachi 2.0 Ton Split	Machine Ok ,Need Service
28	Room No -318	Hitachi 2.0 Ton Split	ODU could not be checked
29	Room No -318	Hitachi 2.0 Ton Split	ODU could not be checked
30	Room No- 313	Voltas 2.0 ton Split	Machine Running Ok, Needs Servicing
31	Room No- 313	Voltas 2.0 ton Split	Machine Running Ok, Needs Servicing
32	Room No- 313	Voltas 2.0 ton Split	Gas Leakage
33	Room No- 314	Voltas 2.0 ton Split	Gas Leakage ,Pipe Line Missing, Need 15 feet 5/8 & 1/4 15 Feet with insulation & Flair Nut
34	Room No- 314	Voltas 2.0 ton Split	Gas Leakage ,Pipe Line Missing, Need 15 feet 5/8 & 1/4 15 Feet with insulation & Flair Nut

Name of the contractor:

Address

Amount /Rate quoted by the contractor:

Signature of contractor