



UNIVERSITY OF CALCUTTA
OFFICE OF THE UNIVERSITY ENGINEER
87/1 College Street
Darbhanga Building, GroundFloor
Kolkata-700073
Website :-www.caluniv.ac.in

NOTICE INVITING TENDER (corrigendum)

University of Calcutta invites **sealed** tender from resourceful and bonafide contractors for the following work

1.	N.I.Q. No	:	Eng /CQ-451/19-20. Dated06/02/2020 (corrigendum)
2.	Name of Work	:	Repairing of furnitures with supplying of office Steel Almirah and other ancillary work at various places and departments at college street campus University of Calcutta
3.	Estimated Cost put to Tender	:-	RsNA
4.	Earnest Money	:-	A sum of 5% of the Quoted amount in the form of CTS demand draft in favour of University of Calcutta payable at Kolkata is to be attached with the Tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenders on application after issuing of work order to the successful bidder. In case of successful tender the EMD will be returned on application after an equal amount of security deposit is deducted by the University from the running bills. EMD is exempted for those bidders who are registered with NSIC or any Government organization- to safeguard against a bidder withdrawing/altering his bid during the bid validity period.
5.	Time of completion	:-	30 DAYS
6.	Eligibility Criteria	:-	Valid trade License , GST & Pan and credential for satisfactory completion of similar nature of job. Amounting 75 % of the estimated value in a single tender in the last three financial year . Government, Government Undertaking and University of Calcutta credentials are accepted.(only completion certificate of the work should be treated as Credential.
7.	Last date of receipt of application for tender	:-	NA
8.	Last date of Sale/ issue of tender papers		TO BE DOWNLOADED FROM WEBSITE.(www. caluniv.ac.in)
9.	Last Date and Time of tender Submission	:-	13/02/2020 up to 2.00pm)
10.	Date and Time of Tender Opening	:-	On or after 3:00 PM 13/02/2020.

N.I.Qno ,Name of work and the date of opening should be written on the sealed envelope otherwise tender will not be opened thus cancelled.

The undersigned reserves the right to reject any or all Tenders without assigning any reason what so ever.

UNIVERSITY ENGINEER (C.U)



UNIVERSITY OF CALCUTTA

Name of the work:-Repairing of furnitures with supplying of office Steel Almirah and other ancillary work at various places and departments at college street campus University of Calcutta

N. I.Q. no- Eng /CQ-451/19-20. **Dated**06/02/2020

Name of Agency:-

Address of Agency:-

Rate Quoted :- (in figure)-

.....

(In words):-

Signature of the Agency with date & stamp:-



UNIVERSITY OF CALCUTTA

N. I.Q. no- Eng /CQ-451/19-20. Dated 06/02/2020

TENDER AND CONTRACT FOR WORK

GENERAL TERMS AND DIRECTION FOR THE GUIDANCE OF CONTRACT

1. Eligible Tenders will have to download the tender papers from the website & drop the filled tender papers signed with seal and date at every page along with copy of Valid Trade license's, GST & PAN and Credential for satisfactory completion of similar nature of job amounting to at least seventy five percent of the job value in a single tender from any Government, Govt. undertaking or University of Calcutta in the last three financial year in sealed envelope in the Tender box kept in the Office of the undersigned with in the specified time mentioned in the NIQ. which will be opened by the undersigned or by his representative with in **the specified time and date mentioned in the NIQ.** **The tendered must write the name of the work ,NIQ no , the date of opening and name of the bidder on the envelop failing which the tender will not be opened thus will be treated as cancelled.**
2. The rate should be quoted after inspection of the site and inclusive of all incidental charges i.e. freight, insurances, labour insurances, handling charges, necessary government taxes, duties etc as well as the Water, Electricity charges which are to be paid as per rules .
3. The contractor shall be responsible to ensure compliance with the provision of minimum wages act 1948 as modified up to date and the rules made in respect of any employees, employed by the contractor directly or through the petty or subcontractor for the purpose of carrying this contract. The contractor shall be responsible for any damage, injury or loss caused by the work or workmen to any person, animal or material during the progress of work.
4. Liquidated damage will be charged to the contractor if they fail to complete the work within the stipulated time, 0.01% per day to a maximum limit of 05 % of the contract value .



5. The allotted time for completion of the work is as specified in the NIQ from the date of receipt of work order. Time is the essence of this contract. Normally no time extension will be granted. In case of prayer for extension of time the University authority has the full right reserved to grant it or discard it.

6. (a) If the successful contractor's bid rate is 80% or less than the estimated amount put to tender the contractor will have to submit a Bank Guarantee amounting to 10% of the Tendered amount before issue of Work order failing which the EMD will be forfeited and the agency may be blacklisted. The Bank Guarantee should be valid till the end of the contract period and shall be renewed accordingly if required. This bank Guarantee is an Additional Performance Security. So provision of deducting Security deposit from bills will hold goods per relevant clause of the contract. The bank Guarantee shall be returned immediately on successful completion of contract.

(b) The University authority will retain a sum amounting to 10% of the bill of the contract for a period of six months from the date of completion of work as **Security Deposit**. Which will be released after a period of six months from the date of completion of the work on application.

7. A sum of 5% of the estimated amount i.e. value **as mentioned in the NIQ** in the form of demand draft in favour of UNIVERSITY OF CALCUTTA payable at Kolkata is to be attached with the tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenderers on application after issue of work order to the successful bidder. For successful tenderer the EMD will be returned on application after an equal amount of security deposit is deducted from the running bills.

Amount:-Rs

D.D No..... Dated / /20

Name of Issuing Bank:--

Branch :-

8. Work is to be carried out as per specification laid in the B.O.Q or PWD specification as per instruction of the University Engineer or his representative.



9.The materials brought to site for execution of the work should by no means be taken out of site without the permission of the Engineer C.U.

10. The rates must be quoted in words in figure other wise the tender will be cancelled.

11. The University will not be bound to accept the lowest bidder.

12.The University will not supply any materials to the contractor.

13. The contractor will work under the strict supervision of the Engineer/ Sub-Assistant Engineer. The estimate given along with the tender are provisional payment will be made on the actual work done jointly measured by the Engineer or his representative(Sub-Assistant Engineer)& the contractor or his representative. The contractor will have to submit bill in printed format in duplicate .

14. The contractor will have to take necessary instruction from the Engineer CU/ Sub-Assistant Engineer regarding the execution of work.

15.Defect & liability Period :-The defect & liability period will be for a period of six months from the date of completion of the job. Any defects pointed out during this period has to be mend good by the agency at their own cost failing which the retention money will be forfeited.

Sd/-

University Engineer

Name of the Agency:

Address :-

SIGNATURE OF THE CONTRACTOR WITH SEAL AND DATE

Name of work:-Repairing of furnitures with supplying of office Steel Almirah and other ancillary work at various places and departments at college street campus University of Calcutta

Sl.no	Description of Work	UNIT	Quantity	Rate	Amount
1	<p>Supplying of office Steel Almirah (Steel Almirah,{ Dimensions 78 x 34 x18 inch.Rack with 5 Compartments of 4 no. of shelves,Standard lock and 2 sets of keys, The thickness of the Almirah sheet shall be 18 SWG. The body of the Almirah shall be manufactured from cold rolled MS sheet (C. R. Sheet) with Antirust treatment and shall be finished with powder coating}at Room no 101,of Asutosh Building(3no) Ground floor ,room of placement officer 7th floor Centenary Building(1no), Room of Gandhi chair professor(1no)darghanga Building first floor, University of Calcutta</p>	each	5		
2	<p>Supply fitting and fixing of of good Quality Curtain with bracket and rod etc(as per Choice of End user the agency must visit site before quoting) at first floor ,Asutosh Museum and Seventh floor Placement officers room at Centenary Building complete in all respect.</p>				
	size				

a	8'-4"x4'-2"	each	13		
b	3'-4"x5'-2"	each	12		
c	2.5mx1.5m	each	3		
3	Necessary repairing, remodeling & polishing the existing wooden top working table with cupboard, drawer etc				
a	6'-00"x4'-0" x2'-6"	each	2		
b	4'-00"x3'-0" x2'-6"	each	1		
c	4'-00"x2'-6" x2'-6"	each	3		
4	Necessary repairing, remodeling & polishing the existing wooden chair with required PU foam, C.C. Cloth etc complete in all respect	each	8		
5	Supply of 6mm clear glass for table top				
a	6'-00"x4'-0"	each	1		
b	6'-00"x2'-6"	each	1		
6	Supply of good quality blazer cloth				
	6'-00"x4'-0"	each	1		
	6'-00"x2'-6"	each	1		
	6'-00"x1'-03"	each			
6	Supply and fixing of 3mm clear glass for wooden almirah				
a	16"x14"	each	12		
b	24"x 12"	each	5		
c	16"x10"	each	1		
7	Supplying fitting and fixing of name plate (Acrylic boards)				
a	Gandhi Chair Professor and Name of individual	each			

b	Officer of placement and training and name of individual	each			
7	<p>Making of Computer comptable from the old tables of (the tables made should be of more or less identical size aprox 3'-06" X2'-06" withtolerence of +/- 06") with space for DRAWER & LOCKER(with godrej lock) on one side. The Front of the table as well as the entire external exposed area should be covered with 5mm ply pasted(withadeshive) with 1mmthick laminate of and the internal part should be polished.The top of the table will be provided withone piece 6mm thick clear glass to fit the size of the table. The glass as well as the table top should have a circular slot to provide cable manager. The Rate should be quoted inclusive costof all new materials needed , labour and any extra materials required other than specified above .(agency should Quote after seeing the site)</p>	each	5		
8	<p>Repairing of the existing chair (with or with out arm) with the seat and back with ply and laminate matching the tables</p>	each	20		

	and the rest part polished complete .(agency should Quote after seeing the site)				
	Total Cost inclusive all taxes				

Name and Address of the Agency:-

Rate Quoted :- (in figure)-

(In words):-

Signature of the Agency with date and seal:-



UNIVERSITY OF CALCUTTA
OFFICE OF THE UNIVERSITY ENGINEER
87/1 College Street
Darbhanga Building, GroundFloor
Kolkata-700073
Website :-www.caluniv.ac.in

NOTICE INVITING TENDER

University of Calcutta invites **sealed** tender from resourceful and bonafide contractors for the following work

1.	N.I.T. No	:	Eng /CT-452/19-20. Dated 07/ 02 / 2020
2.	Name of Work	:	2 nd call for Repairing of shabby wall plaster of toilet side rooms of Annex building at Carmichael Hall, 51, BaithakKhana Road, Kolkata -700 009
3.	Estimated Cost put to Tender	:-	Rs 83,555.41
4.	Earnest Money	:-	A sum of Rs4200/- (RupeesTwoThousand&two hundred only) in the form of CTS demand draft in favour of University of Calcutta payable at Kolkata is to be attached with the Tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenders on application after issuing of work order to the successful bidder. In case of successful tender the EMD will be returned on application after an equal amount of security deposit is ducted by the University from the running bills. EMD is exempted for those bidders who are registered with NSIC or any Government organization- to safeguard against a bidder withdrawing/altering his bid during the bid validity period.
5.	Time of completion	:-	30days
6.	Eligibility Criteria	:-	Valid trade License , GST & Pan and credential for satisfactory completion of similar nature of job. Amounting 75 % of the estimated value in a single tender in the last three financial year . Government, Government Undertaking and University of Calcutta credentials are accepted.(only completion certificate of the work should be treated as Credential.
7.	Last date of receipt of application for tender	:-	NA
8.	Last date of Sale/ issue of tender papers		TO BE DOWNLOADED FROM WEBSITE.(www. caluniv.ac.in)
9.	Last Date and Time of tender Submission	:-	14/02 /2020.(up to 2.00 PM)
10.	Date and Time of Tender Opening	:-	On or after 3:00 14/02 /2020.

N.I.T no ,Name of work and the date of opening should be written on the sealed envelope otherwise tender will not be opened thus cancelled.

The undersigned reserves the right to reject any or all Tenders without assigning any reason what so ever.

UNIVERSITY ENGINEER (C.U)



UNIVERSITY OF CALCUTTA

Name of the work:-2nd call for Repairing of shabby wall plaster of toilet side rooms of Annex building at Carmichael Hall, 51, BaithakKhana Road, Kolkata -700 009

N. I.T. no- Eng /CT-452/19-20. Dated 07/ 02 / 2020

Estimated cost Put to Tender:-Rs**83,555.41**

Name of Agency:-

Address of Agency:-

Rate quoted by Agency:- (%)
Percent Above / At par / Below

Signature of the Agency with date & stamp:-



UNIVERSITY OF CALCUTTA

N. I.T. no- Eng /CT-452/19-20. Dated 07/ 02 / 2020

TENDER AND CONTRACT FOR WORK

GENERAL TERMS AND DIRECTION FOR THE GUIDANCE OF CONTRACT

1. Eligible Tenders will have to download the tender papers from the website & drop the filled tender papers signed with seal and date at every page along with copy of Valid Trade license's, GST & PAN and Credential for satisfactory completion of similar nature of job amounting to at least seventy five percent of the job value in a single tender from any Government, Govt. undertaking or University of Calcutta in the last three financial year in sealed envelope in the Tender box kept in the Office of the undersigned with in the specified time mentioned in the NIT. which will be opened by the undersigned or by his representative with in **the specified time and date mentioned in the NIT.** **The tendered must write the name of the work , NIT no , the date of opening and name of the bidder on the envelop failing which the tender will not be opened thus will be treated as cancelled.**
2. The rate should be quoted after inspection of the site and inclusive of all incidental charges i.e. freight, insurances, labour insurances, handling charges, necessary government taxes, duties etc as well as the Water, Electricity charges which are to be paid as per rules .
3. The contractor shall be responsible to ensure compliance with the provision of minimum wages act 1948 as modified up to date and the rules made in respect of any employees, employed by the contractor directly or through the petty or subcontractor for the purpose of carrying this contract. The contractor shall be responsible for any damage, injury or loss caused by the work or workmen to any person, animal or material during the progress of work.
4. Liquidated damage will be charged to the contractor if they fail to complete the work within the stipulated time, 0.01% per day to a maximum limit of 05 % of the contract value .



5. The allotted time for completion of the work is as specified in the NIT from the date of receipt of work order. Time is the essence of this contract. Normally no time extension will be granted. In case of prayer for extension of time the University authority has the full right reserved to grant it or discard it.

6. (a) If the successful contractor's bid rate is 80% or less than the estimated amount put to tender the contractor will have to submit a Bank Guarantee amounting to 10% of the Tendered amount before issue of Work order failing which the EMD will be forfeited and the agency may be blacklisted. The Bank Guarantee should be valid till the end of the contract period and shall be renewed accordingly if required. This bank Guarantee is an Additional Performance Security. So provision of deducting Security deposit from bills will hold goods per relevant clause of the contract. The bank Guarantee shall be returned immediately on successful completion of contract.

(b) The University authority will retain a sum amounting to 10% of the bill of the contract for a period of six months from the date of completion of work as **Security Deposit**. Which will be released after a period of six months from the date of completion of the work on application.

7. A sum of 5% of the estimated amount i.e. value **as mentioned in the NIT** in the form of demand draft in favour of UNIVERSITY OF CALCUTTA payable at Kolkata is to be attached with the tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenderers on application after issue of work order to the successful bidder. For successful tenderer the EMD will be returned on application after an equal amount of security deposit is deducted from the running bills.

Amount:-Rs

D.D No..... Dated / /20

Name of Issuing Bank:--

Branch :-

8. Work is to be carried out as per specification laid in the B.O.Q or PWD specification as per instruction of the University Engineer or his representative.



9.The materials brought to site for execution of the work should by no means be taken out of site without the permission of the Engineer C.U.

10. The rates must be quoted in words in figure other wise the tender will be cancelled.

11. The University will not be bound to accept the lowest bidder.

12.The University will not supply any materials to the contractor.

13. The contractor will work under the strict supervision of the Engineer/ Sub-Assistant Engineer. The estimate given along with the tender are provisional payment will be made on the actual work done jointly measured by the Engineer or his representative(Sub-Assistant Engineer)& the contractor or his representative. The contractor will have to submit bill in printed format in duplicate .

14. The contractor will have to take necessary instruction from the Engineer CU/ Sub-Assistant Engineer regarding the execution of work.

15.Defect & liability Period :-The defect & liability period will be for a period of six months from the date of completion of the job. Any defects pointed out during this period has to be mend good by the agency at their own cost failing which the retention money will be forfeited.

Sd/-

University Engineer

Name of the Agency:

Address :-

SIGNATURE OF THE CONTRACTOR WITH SEAL AND DATE

Specific price schedule for repairing of shabby wall plaster of toilet side rooms of Annex building at Carmichael Hall, 51, BaithakKhana Road, Kolkata -700 009

Rates according to P. W. D. Schedule 2017 (Effective From 01.11.2017)

Item	Description	Quantity	Rate	Amount (Rs.)
1	Stripping off worn out plaster and raking out joints of walls, ceilings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed (Page- 11 / Sl. No. 10)	241.80 Sq.m.	Rs.19.00 per Sq.m.	4594.20
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary. With 1:6 cement mortar 15 mm thick plaster (Page- 189 / Sl. No. 1ic)	241.80 Sq.m.	Rs.145.00 per Sq.m.	35061.00
3	Applying 2 coats of bonding agent with synthetic multi functional rubber emulsion having adhesive and water proofing properties by mixing with water in proportion (1 bonding agent : 4 water : 6 cement) as per Manufacturer's specification. (Page- 45 / Sl. No. 8a)	241.80 Sq.m.	Rs.88.00 per Sq.m.	21278.40
4	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC. Two Coats Solvent based interior grade Acrylic Primer. (Page- 195 / Sl. No. 7bii)	241.80 Sq.m.	Rs.48.50 per Sq.m.	11727.30
5	Removal of rubbish,earth etc. from the working site and disposal of the same beyond the compound, in conformity with the Municipal /Corporation Rules for such disposal, loading into truck and cleaning the site in all respect as per direction of Engineer in charge. (Page- 12 / Sl. No. 13)	7.25 Cum.	Rs.166.00 per Cum.	1203.50
Tentative Basic Cost =				
Rs.				73,864.40
GST @ 12 % (to be confirm by concern authority)			Rs.	8863.73
Cost of civil works excluding labour welfare cess			Rs.	82,728.13
Labour welfare cess @1%			Rs.	827.28
Cost of civil works including labour welfare cess - Total Cost			Rs.	83,555.41

Name Of The Agency:

Address Of The Agency:

Rate quoted by the Agency: (.....%)

Percent Below/ At Par/ Above



UNIVERSITY OF CALCUTTA
OFFICE OF THE UNIVERSITY ENGINEER
87/1 College Street
Darbhanga Building, GroundFloor
Kolkata-700073
Website :-www.caluniv.ac.in

NOTICE INVITING TENDER

University of Calcutta invites **sealed** tender from resourceful and bonafide contractors for the following work

1.	N.I.T. No	:	Eng /CT-453/19-20. Dated 07/ 02 / 2020
2.	Name of Work	:	Repairing & Painting of Room of the Gandhi Chair Professor 1st floor Darbhanga Building College street Campus.University of Calcutta
3.	Estimated Cost put to Tender	:-	Rs 137046.89
4.	Earnest Money	:-	A sum of Rs6900/- (Rupees six Thousand & nine hundred only) in the form of CTS demand draft in favour of University of Calcutta payable at Kolkata is to be attached with the Tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenders on application after issuing of work order to the successful bidder. In case of successful tender the EMD will be returned on application after an equal amount of security deposit is deducted by the University from the running bills. EMD is exempted for those bidders who are registered with NSIC or any Government organization- to safeguard against a bidder withdrawing/altering his bid during the bid validity period.
5.	Time of completion	:-	10days
6.	Eligibility Criteria	:-	Valid trade License , GST & Pan and credential for satisfactory completion of similar nature of job. Amounting 75 % of the estimated value in a single tender in the last three financial year . Government, Government Undertaking and University of Calcutta credentials are accepted.(only completion certificate of the work should be treated as Credential.
7.	Last date of receipt of application for tender	:-	NA
8.	Last date of Sale/ issue of tender papers		TO BE DOWNLOADED FROM WEBSITE.(www. caluniv.ac.in)
9.	Last Date and Time of tender Submission	:-	14/02 /2020.(up to 2.00 PM)
10.	Date and Time of Tender Opening	:-	On or after 3:00 14/02 /2020.

N.I.T no ,Name of work and the date of opening should be written on the sealed envelope otherwise tender will not be opened thus cancelled.

The undersigned reserves the right to reject any or all Tenders without assigning any reason what so ever.

UNIVERSITY ENGINEER (C.U)



UNIVERSITY OF CALCUTTA

Name of the work:-Repairing & Painting of Room of the Gandhi Chair Professor 1st floor Darbhanga Building College street Campus.University of Calcutta

N. I.T. no- Eng /CT-453/19-20. Dated 07/ 02 / 2020

Estimated cost Put to Tender:-Rs137046.89

Name of Agency:-

Address of Agency:-

Rate quoted by Agency:- (%)
Percent Above / At par / Below

Signature of the Agency with date & stamp:-



UNIVERSITY OF CALCUTTA

N. I.T. no- Eng /CT-453/19-20. Dated 07/ 02 / 2020

TENDER AND CONTRACT FOR WORK

GENERAL TERMS AND DIRECTION FOR THE GUIDANCE OF CONTRACT

1. Eligible Tenders will have to download the tender papers from the website & drop the filled tender papers signed with seal and date at every page along with copy of Valid Trade license's, GST & PAN and Credential for satisfactory completion of similar nature of job amounting to at least seventy five percent of the job value in a single tender from any Government, Govt. undertaking or University of Calcutta in the last three financial year in sealed envelope in the Tender box kept in the Office of the undersigned with in the specified time mentioned in the NIT. which will be opened by the undersigned or by his representative with in **the specified time and date mentioned in the NIT.** **The tendered must write the name of the work , NIT no , the date of opening and name of the bidder on the envelop failing which the tender will not be opened thus will be treated as cancelled.**
2. The rate should be quoted after inspection of the site and inclusive of all incidental charges i.e. freight, insurances, labour insurances, handling charges, necessary government taxes, duties etc as well as the Water, Electricity charges which are to be paid as per rules .
3. The contractor shall be responsible to ensure compliance with the provision of minimum wages act 1948 as modified up to date and the rules made in respect of any employees, employed by the contractor directly or through the petty or subcontractor for the purpose of carrying this contract. The contractor shall be responsible for any damage, injury or loss caused by the work or workmen to any person, animal or material during the progress of work.
4. Liquidated damage will be charged to the contractor if they fail to complete the work within the stipulated time, 0.01% per day to a maximum limit of 05 % of the contract value .



5. The allotted time for completion of the work is as specified in the NIT from the date of receipt of work order. Time is the essence of this contract. Normally no time extension will be granted. In case of prayer for extension of time the University authority has the full right reserved to grant it or discard it.

6. (a) If the successful contractor's bid rate is 80% or less than the estimated amount put to tender the contractor will have to submit a Bank Guarantee amounting to 10% of the Tendered amount before issue of Work order failing which the EMD will be forfeited and the agency may be blacklisted. The Bank Guarantee should be valid till the end of the contract period and shall be renewed accordingly if required. This bank Guarantee is an Additional Performance Security. So provision of deducting Security deposit from bills will hold goods per relevant clause of the contract. The bank Guarantee shall be returned immediately on successful completion of contract.

(b) The University authority will retain a sum amounting to 10% of the bill of the contract for a period of six months from the date of completion of work as **Security Deposit**. Which will be released after a period of six months from the date of completion of the work on application.

7. A sum of 5% of the estimated amount i.e. value **as mentioned in the NIT** in the form of demand draft in favour of UNIVERSITY OF CALCUTTA payable at Kolkata is to be attached with the tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenderers on application after issue of work order to the successful bidder. For successful tenderer the EMD will be returned on application after an equal amount of security deposit is deducted from the running bills.

Amount:-Rs

D.D No..... Dated / /20

Name of Issuing Bank:--

Branch :-

8. Work is to be carried out as per specification laid in the B.O.Q or PWD specification as per instruction of the University Engineer or his representative.



9.The materials brought to site for execution of the work should by no means be taken out of site without the permission of the Engineer C.U.

10. The rates must be quoted in words in figure other wise the tender will be cancelled.

11. The University will not be bound to accept the lowest bidder.

12.The University will not supply any materials to the contractor.

13. The contractor will work under the strict supervision of the Engineer/ Sub-Assistant Engineer. The estimate given along with the tender are provisional payment will be made on the actual work done jointly measured by the Engineer or his representative(Sub-Assistant Engineer)& the contractor or his representative. The contractor will have to submit bill in printed format in duplicate .

14. The contractor will have to take necessary instruction from the Engineer CU/ Sub-Assistant Engineer regarding the execution of work.

15.Defect & liability Period :-The defect & liability period will be for a period of six months from the date of completion of the job. Any defects pointed out during this period has to be mend good by the agency at their own cost failing which the retention money will be forfeited.

Sd/-

University Engineer

Name of the Agency:

Address :-

SIGNATURE OF THE CONTRACTOR WITH SEAL AND DATE

Specific Price Schedule for Repairing & Painting of Room of the Gandhi Chair Professor 1st floor Darbhanga Building College street Campus.University of Calcutta

SI No	Description of Work	Unit	Rate	Quantity	Amount
1	Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed.	Sqm	19.00	103.40	1964.60
2	Removal of rubbish,earth etc. from the working site and disposal of the same beyond the compound, in conformity with the Municipal / Corporation Rules for such disposal, loading into truck and cleaning the site in all respect as per direction of Engineer in charge	Cum	166.00	2.07	343.29
3	Applying 2 coats of bonding agent with synthetic multi functionalrubberemulsion having adhesive and water proofing properties by mixing with water in proportion (1 bonding agent : 4 water : 6 cement) as per Manufacturer's specification [Cement to be supplied by the Department]	Sqm	88.00	51.00	4488.00
4	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).With 1:6 cement mortar (a) 20 mm thick plaster	Sqm	167.00	109.86	18346.62
5	Brick work with 1st class bricks in cement mortar (1:4)	Cum	5798.00	4.01	23264.48
6	Rendering the Surface of walls and ceiling with White Cement base WATER PROOF wall putty of approved make & brand.(1.5 mm thick	Sqm	122.00	103.40	12614.80
7	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface throughly, complete as per manufacturer's specification and as per direction of the EIC. (In Ground Floor) (a) One Coat i) Water based interior grade Acrylic Primer	Sqm	30.80	101.82	3135.93
8	Applying Acrylic Emulsion Paint of approved make and brand on walls and ceiling including sand paping in intermediate coats including putty (to be done under specific instruction of Superintending Engineer) : (Two coats)ii) Luxury Quality	Sqm	70.00	101.82	7127.40

9	(b) Priming one coat on timber or plastered surface with synthetic oilbound primer of approved quality including smoothening surfaces by sand papering etc.	Sqm	38.00	18.72	711.36
10	Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary :				
	(a) On timber or plastered surface :With super gloss (hi-gloss) - (iv) Two coats (with any shade except white)	Sqm	81.00	18.72	1516.32
11	Providing and fixing of false ceiling with powder coated exposed G.I. gridsuspension system (E-Grid T 2430/1510 or equivalent load carrying capacity with mid span deflection not exceeding 1/360 span with hanger spacing of 1200mm c/c) consisting of Main Runner 3600 mm long, Cross Tee 1200 mm / 600 mm longand Wall Angle. The Wall Angle shall be fixed on PVC Dash Fasteners on theperimeter of the wall by steel screws with distance 300mm c/c. The Main Runnerstobe placed @ 1200 mm. The Cross Tee 1200mm will be inserted in the pre-cutslots of Main Runner at a regular interval of 600 mm to form a modular grid of1200mm X 600mm. Additional Cross Tees of 600 mm shall be placedperpendicular to the Cross Tee 1200 mm long to finally form a grid of 600 mm X600 mm. Grid of module size 600 mm X 600 mm shall be supported by 6 mm diaG.I. wire from purlins / soffit. 4 mm thick High Pressure Steam Cured NonAsbestos pearl designer Fibre Cement Standard Ceiling Board (Density > 1500Kg/m3) of size 595 mm X 595 mm, conforming IS 14862 & Type A Category IV of ISO 8336, tested as per AS-1530 part 3 & BS-476 Part 4,5,6,7 & 8, should beplaced in the Grid module to form a False Ceiling. All complete as per thedrawing& directions of Engineer-in-charge.In ground floor	Sqm	686.00	21.45	14714.7
12	Supplying and laying true to line and level vitrified tiles ofapproved brand (size not less than 600 mm X 600 mm X 10mm thick) in floor, skirting etc. set in 20 mm sand cementmortar (1:4) and 2 mm thick cement slurry back side of tilesusing cement @ 2.91Kg./sqM or using polymerised adhesive(6 mm thick layer applied directly over finished artificial stone floor/Mosaic etc without any backing course) laid after application slurry using 1.75 Kg of cement per sqMbelowmortar only, joints grouted with admixture of white cementandcolouring pigment to match with colour of tiles / epoxygrout materials of approved make as directed and removal ofwax coating of top surface of tiles with warm water andpolishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials, labour and all otherincidental charges complete true to the manufacturer'sspecification and direction of Engineer-in-Charge. (Whitecement, synthetic adhesive and grout material to be suppliedby the contrr]e)				

	With Polymerised Adhesive [6 mm thick] & epoxy grouting materials for filling joints including spacer-2 mmA)				
	Light Colour	Sqm	1276.00	22.04	28123.04
13	Labour for Chipping of concrete surface before taking up Plastering work.	Sqm	21.00	22.04	462.84
14	SUPPLYING labour for dismantelling and removing jailytegate,door& window and refixing a door .				
a	welder	NOS	358.60	2.00	717.2
b	carpenter	NOS	358.60	3.00	1075.8
c	Carpenter helper	NOS	297.00	5.00	1485
15	Supplying best Indian sheet glass panes set in putty and fitted and fixedwith nails and putty complete. (In all floors for internal wall &upto 6m height for external wall)Page::-205,Item no-1,(ii),pwd17	Sqm	477.00	1.20	572.4
16	Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark.				
	(vi) 100mm. X 50mm. X 1.25mm.	Each	47.00	6.00	282
17	Anodisedaluminium D-type handle of approved quality manufactured from extruded section conforming to I.S. specification (I.S. 230/72) fitted and fixed complete:	Each	103.00	2.00	206
A	Total Tentative Basic cost				121151.78
B	Goods & Service Tax onA@12%				14538.21
C	Total Tentative cost+GST (A+B)				135689.99
D	ADD 1% Labour Welfare Cess on C				1356.90
					137046.89

Name Of The Agency:

Address Of The Agency:

Rate quoted by the Agency: (.....%)
Percent Below/ At Par/ Above



UNIVERSITY OF CALCUTTA
OFFICE OF THE UNIVERSITY ENGINEER
87/1 College Street
Darbhanga Building, GroundFloor
Kolkata-700073
Website :-www.caluniv.ac.in

NOTICE INVITING TENDER

University of Calcutta invites **sealed** tender from resourceful and bonafide contractors for the following work

1.	N.I.T. No	:	Eng /CT-454/19-20. Dated 07/ 02 / 2020
2.	Name of Work	:	Repairing Renovation & Painting of the Room allotted to IQAC at 3rd floor ,Darbhanga and Room of the Placement officer at 7th floor Centenary buildingCollege street University of Calcutta
3.	Estimated Cost put to Tender	:-	Rs132577.47
4.	Earnest Money	:-	A sum of Rs6650/- (Rupees six Thousand six hundred and fifty only) in the form of CTS demand draft in favour of University of Calcutta payable at Kolkata is to be attached with the Tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenders on application after issuing of work order to the successful bidder. In case of successful tender the EMD will be returned on application after an equal amount of security deposit is ducted by the University from the running bills. EMD is exempted for those bidders who are registered with NSIC or any Government organization- to safeguard against a bidder withdrawing/altering his bid during the bid validity period.
5.	Time of completion	:-	10days
6.	Eligibility Criteria	:-	Valid trade License , GST & Pan and credential for satisfactory completion of similar nature of job. Amounting 75 % of the estimated value in a single tender in the last three financial year . Government, Government Undertaking and University of Calcutta credentials are accepted.(only completion certificate of the work should be treated as Credential.
7.	Last date of receipt of application for tender	:-	NA
8.	Last date of Sale/ issue of tender papers		TO BE DOWNLOADED FROM WEBSITE.(www. caluniv.ac.in)
9.	Last Date and Time of tender Submission	:-	14/02 /2020.(up to 2.00 PM)
10.	Date and Time of Tender Opening	:-	On or after 3:00 14/02 /2020.

N.I.T no ,Name of work and the date of opening should be written on the sealed envelope otherwise tender will not be opened thus cancelled.

The undersigned reserves the right to reject any or all Tenders without assigning any reason what so ever.

UNIVERSITY ENGINEER (C.U)



UNIVERSITY OF CALCUTTA

Name of the work:-Repairing Renovation & Painting of the Room allotted to IQAC at 3rd floor ,Darbhanga and Room of the Placement officer at 7th floor Centenary buildingCollege street University of Calcutta

N. I.T. no- Eng /CT-454/19-20. **Dated** 07/ 02 / 2020

Estimated cost Put to Tender:-Rs132577.47

Name of Agency:-

Address of Agency:-

Rate quoted by Agency:- (%)
Percent Above / At par / Below

Signature of the Agency with date & stamp:-



UNIVERSITY OF CALCUTTA

N. I.T. no- Eng /CT-454/19-20. **Dated** 07/ 02 / 2020

TENDER AND CONTRACT FOR WORK

GENERAL TERMS AND DIRECTION FOR THE GUIDANCE OF CONTRACT

1. Eligible Tenders will have to download the tender papers from the website & drop the filled tender papers signed with seal and date at every page along with copy of Valid Trade license's, GST & PAN and Credential for satisfactory completion of similar nature of job amounting to at least seventy five percent of the job value in a single tender from any Government, Govt. undertaking or University of Calcutta in the last three financial year in sealed envelope in the Tender box kept in the Office of the undersigned with in the specified time mentioned in the NIT. which will be opened by the undersigned or by his representative with in **the specified time and date mentioned in the NIT.** **The tendered must write the name of the work , NIT no , the date of opening and name of the bidder on the envelop failing which the tender will not be opened thus will be treated as cancelled.**
2. The rate should be quoted after inspection of the site and inclusive of all incidental charges i.e. freight, insurances, labour insurances, handling charges, necessary government taxes, duties etc as well as the Water, Electricity charges which are to be paid as per rules .
3. The contractor shall be responsible to ensure compliance with the provision of minimum wages act 1948 as modified up to date and the rules made in respect of any employees, employed by the contractor directly or through the petty or subcontractor for the purpose of carrying this contract. The contractor shall be responsible for any damage, injury or loss caused by the work or workmen to any person, animal or material during the progress of work.
4. Liquidated damage will be charged to the contractor if they fail to complete the work within the stipulated time, 0.01% per day to a maximum limit of 05 % of the contract value .



5. The allotted time for completion of the work is as specified in the NIT from the date of receipt of work order. Time is the essence of this contract. Normally no time extension will be granted. In case of prayer for extension of time the University authority has the full right reserved to grant it or discard it.

6. (a) If the successful contractor's bid rate is 80% or less than the estimated amount put to tender the contractor will have to submit a Bank Guarantee amounting to 10% of the Tendered amount before issue of Work order failing which the EMD will be forfeited and the agency may be blacklisted. The Bank Guarantee should be valid till the end of the contract period and shall be renewed accordingly if required. This bank Guarantee is an Additional Performance Security. So provision of deducting Security deposit from bills will hold goods per relevant clause of the contract. The bank Guarantee shall be returned immediately on successful completion of contract.

(b) The University authority will retain a sum amounting to 10% of the bill of the contract for a period of six months from the date of completion of work as **Security Deposit**. Which will be released after a period of six months from the date of completion of the work on application.

7. A sum of 5% of the estimated amount i.e. value **as mentioned in the NIT** in the form of demand draft in favour of UNIVERSITY OF CALCUTTA payable at Kolkata is to be attached with the tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenderers on application after issue of work order to the successful bidder. For successful tenderer the EMD will be returned on application after an equal amount of security deposit is deducted from the running bills.

Amount:-Rs

D.D No..... Dated / /20

Name of Issuing Bank:--

Branch :-

8. Work is to be carried out as per specification laid in the B.O.Q or PWD specification as per instruction of the University Engineer or his representative.



9.The materials brought to site for execution of the work should by no means be taken out of site without the permission of the Engineer C.U.

10. The rates must be quoted in words in figure other wise the tender will be cancelled.

11. The University will not be bound to accept the lowest bidder.

12.The University will not supply any materials to the contractor.

13. The contractor will work under the strict supervision of the Engineer/ Sub-Assistant Engineer. The estimate given along with the tender are provisional payment will be made on the actual work done jointly measured by the Engineer or his representative(Sub-Assistant Engineer)& the contractor or his representative. The contractor will have to submit bill in printed format in duplicate .

14. The contractor will have to take necessary instruction from the Engineer CU/ Sub-Assistant Engineer regarding the execution of work.

15.Defect & liability Period :-The defect & liability period will be for a period of six months from the date of completion of the job. Any defects pointed out during this period has to be mend good by the agency at their own cost failing which the retention money will be forfeited.

Sd/-

University Engineer

Name of the Agency:

Address :-

SIGNATURE OF THE CONTRACTOR WITH SEAL AND DATE

Specific price Schedule for Repairing Renovation & Painting of the Room allotted to IQAC at 3rd floor ,Darbhanga and Room of the Placement officer at 7th floor Centenary building College street University of Calcutta

Sl.no	PWD SOR	Description Of Work	Unit	Rate	Quantity	Amount
1		Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed	Sq.M	19	57.2	1086.8
2		Removal of rubbish,earth etc. from the working site and disposal of the same beyond the compound, in conformity with the Municipal / Corporation Rules for such disposal, loading into truck and cleaning the site in all respect as per direction of Engineer in charge	Cu.M.	166	2	332
3		Applying 2 coats of Non-Toxic Acrylic Polymer modified Paint having adhesive & waterproofing properties by mixing in proportion (1 liquid: 4 cementitious material) or as per manufacturer's specification for water proofing layer in water tank etc. (No Departmental Cement is required)	Sq. M	88	30	2640
4		Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (i) With 1:6 cement mortar (b) 20 mm thick plaster	Sq. M	167.00	60.00	10020.00
5		Rendering the Surface of walls and ceiling with White Cement base WATER PROOF wall putty of approved make & brand.(1.5 mm thick) ground floor including roof	SqM	122	60.00	7320

6		Taking out shutter of door and window, dismantling by parts (for repair or replacement of damaged parts) , reassembling and refitting and rehangng same with old fittings but with new screws as necessary. (Where different parts of same shutter are renewed under different item, payment under item 73 will be made once only).	SqM	126	3.6	453.6
7		Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface throughly, complete as per manufacturer's specification and as per direction of the EIC. (In Ground Floor)				
		In Ground Floor:				
		i) Water based interior grade Acrylic Primer	Sq.M	30.8	60	1848
8		Applying Acrylic Emulsion Paint of approved make and brand on walls and ceiling including sand papering in intermediate coats including putty: (Two coats)Luxury Quality	Sq.M	70	60	4200
9		Supplying, fitting and fixing boiling water resistant ply conforming to IS: 303-1989 bonded with phenol formaldehyde synthetic resin of approved make and brand fitted and fixed as per design as per approval and direction of Engineer-in-Charge.[excluding the cost of supporting frame work and teak wood batten/Lipping] In Ground Floor				
		(ii) 6mm	Sq.M	923	0.9	830.70
10		(b) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	Sq.M	38	19	722

11		(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary :				
		(a) On timber or plastered surface :With super gloss (hi-gloss) -Two coats (with any shade except white)	SqM	81	19	1539.00
12		(A) Providing and fixing of false ceiling with powder coated exposed G.I. grid suspension system (E-Grid T 2430 or equivalent load carrying capacity with mid span deflection not exceeding 1/360 span with hanger spacing of 1200mm c/c) consisting of Main Runner 3600 mm long, Cross Tee 1200 mm / 600 mm long and Wall Angle. The Wall Angle shall be fixed on PVC Dash Fasteners on the perimeter of the wall by steel screws with distance 300mm c/c. The Main Runners to be placed @ 1200 mm. The Cross Tee 1200mm will be inserted in the pre-cut slots of Main Runner at a regular interval of 600 mm to form a modular grid of 1200mm X 600mm. Additional Cross Tees of 600 mm shall be placed perpendicular to the Cross Tee 1200 mm long to finally form a grid of 600 mm X 600 mm. Grid of module size 600 mm X 600 mm shall be supported by 6 mm dia G.I. wire from purlins / soffit. 6 mm thick High Pressure Steam Cured Non Asbestos Fibre Cement Standard Ceiling Board (Density > 1300 Kg/m ³) of size 595 mm X 595 mm, conforming IS 14862 & Type B Category III of ISO 8336, tested as per AS-1530 part 3 & BS-476 Part 4,5,6,7 & 8, should be placed in the Grid module to form a False Ceiling. All complete as per the drawing & directions of Engineer-in-charge. In ground floor.				
		A) False Ceiling (with 6mm thick Fibre Cement Designer Board and E-Grid T-2430).	Sqm	686	16	10976.00
13		Cleaning glazed tiles with acid.	SqM	10	16	160

14		Flush pointing to tiled floor in cement mortar (1:4) with admixture of pigment to match with colour of tiles including raking out joints.	SqM	79	16	1264
15		Supplying profiles of required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285-1975; Anodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composite door, sliding & casement windows, partitions, formed of basic sections of any IS embossed / certified make and brand as per direction of Engineer - In-Charge. (Payment will be made on finished length of the work). (A) In 10-12 Micron thickness Anodizing film				
		j) Fixed partitions. (Unsupported length of vertical member upto 1.5 mtr. Height of both ends of vertical member restrained but panels within 0.9 sq.m.)				
		i) Top, bottom & side member.	Sq.M	462	20.4	9424.8
		ii) Intermediate member.	Sq.M	480	30.9	14832
		iii) Glazing clip.	Sq.M	46	112.8	5188.8
16		Labour charge for fabrication and installation of composite door, window, partitions made from anodized extruded alloy aluminium sections for the following units:-				

	(D) Partly glazed and partly panelled partition or fixed glazing made of extruded and anodised alloy aluminium sections, fabrications after cutting to proper shape and size, drilling and aligning fitted with inbuilt locking arrangement cutting the glass / board (prelaminated / particle / block) to requisite shape and size moulding the edges fitted and fixed glazing clips and dry set neoprine /EPDM gasket, along with all other necessary arrangements for fixing the partition to walls, floors, beams, columns polysulphide sealant for water proofing if necessary complete in all respect as per drawing and specifications and direction of the Engineer in charge..				
	l) For partitions using section of size:				
	a) 63.50 mm x 38.10 mm	Sq.M	728	23	16744
				22	
17	Supplying, fitting & fixing of partly glazed partly panelled or fully glazed single leaf Aluminium swing door of all aluminium sections viz doorframe (top and side frame), shutter(top rail, bottom rail, lock rail, door vertical) , glazing clip made of Aluminium Alloy Extrusions conforming to IS: 733-1983 and IS: 1285-1975, anodized conforming to IS:1868-1983, fitted with all other accessories viz. EPDM gasket, cleat, angle screws etc. including labour charges for fitting and fixing of aluminium door with door spring, /aluminium hinges, glass / Panel board all complete as per architectural drawings and direction of Engineer-incharge. (Excluding cost of glass/ panel board, door spring/ Al hinges, door closer, door stopper, handle, tower bolt and locking arrangement etc) 10-12 Micron thickness Anodizing film Natural white	Kg	385	18.9	7276.50
18	Supplying bubble free float glass of approved make and brand conforming to IS: 2835-1987.				
	iv) 5mm thick coloured / tinted / smoke glass.	Sq.M	585.00	4.02	2351.7

19	Providing, fitting and fixing in position, medium density fibre board conforming to IS: 12406-1988 for plain and IS: 14587-1998 for prelaminated made of wood fibre bonded with Urea formaldehyde for interior grade and Phenol Formaldehyde for exterior grade conforming to per IS:848-1974 as per approved make and brand as per direction of Engineer-in-Charge.In Ground Floor					
	(C) Both side decorative lamination					
	(II) Interior Grade (i) 8mm	Sq.M	781.00	19.43	15174.83	
20	(a) Supplying 'Godrej' mortice lock chromium plated with latch and keys 4 levers, including fitting and fixing complete.	Each	1081	1	1081.00	
21	(ii) Door stopper (Anodisedaluminium)	Each	70	1	70.00	
22	ii) Godrej Hydraulic door closer fitted and fixed complete.(b) Medium type	Each	1665	1	1665.00	
A	Total Tentative Basic Cost					117200.73
B	Goods And Service Tax on A@12%					14,064.09
C	Total Tentative Cost + GST(A+B)					131264.82
D	Add 1% Labour Welfare Cess on C					1312.65
	Total Estimated Cost					132577.47

Name Of The Agency:

Address Of The Agency:

Rate quoted by the Agency: (.....%)
Percent Below/ At Par/ Above