



UNIVERSITY OF CALCUTTA
OFFICE OF THE UNIVERSITY ENGINEER
87/1 College Street
Darbhanga Building, GroundFloor
Kolkata-700073
Website :-www.caluniv.ac.in

NOTICE INVITING TENDER

University of Calcutta invites **sealed** tender from resourceful and bonafide contractors for the following work

1.	N.I.T. No	:	Eng /CT-290/19-20. Dated13/ 11 / 2019
2.	Name of Work	:	Urgent plumbing and carpentry works in toilets of old hostel building at Carmichael Hall, 51, BaithakKhana Road, Kolkata -700 009
3.	Estimated Cost put to Tender	:-	Rs19,736.27
4.	Earnest Money	:-	A sum of Rs1000/- (Rupeesone thousandonly)in the form of CTS demand draft in favour of University of Calcutta payable at Kolkata is to be attached with the Tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenders on application after issuing of work order to the successful bidder. In case of sucessful tender the EMD will be returned on application after an equal amount of security deposit is ducted by the University from the running bills. EMD is exempted for those bidders who are registered with NSIC or any Government organization- to safeguard against a bidder withdrawing/altering his bid during the bid validity period.
5.	Time of completion	:-	30 days
6.	Eligibility Criteria	:-	Valid trade License , GST & Pan and credential for satisfactory completion of similar nature of job. Amounting 75 % of the estimated value in a single tender in the last three financial year . Government, Government Undertaking and University of Calcutta credentials are accepted.(only completion certificate of the work should be treated as Credential.
7.	Last date of receipt of application for tender	:-	07/11/2019.(up to 2.00 PM)
8.	Last date of Sale/ issue of tender papers		08/11/2019.(up to 2.00 PM)
9.	Last Date and Time of tender Submission	:-	13/11/2019.(up to 2.00 PM)
10.	Date and Time of Tender Opening	:-	On or after 3:00 PM 13/11/2019

N.I.T no ,Name of work and the date of opening should be written on the sealed envelope otherwise tender will not be opened thus cancelled.

The undersigned reserves the right to reject any or all Tenders without assigning any reason what so ever.

UNIVERSITY ENGINEER (C.U)



UNIVERSITY OF CALCUTTA

Name of the work:-Urgent plumbing and carpentry works in toilets of old hostel building at Carmichael Hall, 51, BaithakKhana Road, Kolkata -700 009

N. I.T. no- Eng /CT-290/19-20. Dated13/ 11 / 2019

Estimated cost Put to Tender:-Rs**19,736.27**

Name of Agency:-

Address of Agency:-

Rate quoted by Agency:- (%)
Percent Above / At par / Below

Signature of the Agency with date & stamp:-



UNIVERSITY OF CALCUTTA

N. I.T. no- Eng /CT-290/19-20. **Dated**13/ 11 / 2019

TENDER AND CONTRACT FOR WORK

GENERAL TERMS AND DIRECTION FOR THE GUIDANCE OF CONTRACT

1. Eligible Tenders will have to download the tender papers from the website & drop the filled tender papers signed with seal and date at every page along with copy of Valid Trade license's, GST & PAN and Credential for satisfactory completion of similar nature of job amounting to at least seventy five percent of the job value in a single tender from any Government, Govt. undertaking or University of Calcutta in the last three financial year in sealed envelope in the Tender box kept in the Office of the undersigned with in the specified time mentioned in the NIT. which will be opened by the undersigned or by his representative with in **the specified time and date mentioned in the NIT.** **The tendered must write the name of the work , NIT no , the date of opening and name of the bidder on the envelop failing which the tender will not be opened thus will be treated as cancelled.**
2. The rate should be quoted after inspection of the site and inclusive of all incidental charges i.e. freight, insurances, labour insurances, handling charges, necessary government taxes, duties etc as well as the Water, Electricity charges which are to be paid as per rules .
3. The contractor shall be responsible to ensure compliance with the provision of minimum wages act 1948 as modified up to date and the rules made in respect of any employees, employed by the contractor directly or through the petty or subcontractor for the purpose of carrying this contract. The contractor shall be responsible for any damage, injury or loss caused by the work or workmen to any person, animal or material during the progress of work.
4. Liquidated damage will be charged to the contractor if they fail to complete the work within the stipulated time, 0.01% per day to a maximum limit of 05 % of the contract value .



5. The allotted time for completion of the work is as specified in the NIT from the date of receipt of work order. Time is the essence of this contract. Normally no time extension will be granted. In case of prayer for extension of time the University authority has the full right reserved to grant it or discard it.

6. (a) If the successful contractor's bid rate is 80% or less than the estimated amount put to tender the contractor will have to submit a Bank Guarantee amounting to 10% of the Tendered amount before issue of Work order failing which the EMD will be forfeited and the agency may be blacklisted. The Bank Guarantee should be valid till the end of the contract period and shall be renewed accordingly if required. This bank Guarantee is an Additional Performance Security. So provision of deducting Security deposit from bills will hold goods per relevant clause of the contract. The bank Guarantee shall be returned immediately on successful completion of contract.

(b) The University authority will retain a sum amounting to 10% of the bill of the contract for a period of six months from the date of completion of work as **Security Deposit**. Which will be released after a period of six months from the date of completion of the work on application.

7. A sum of 5% of the estimated amount i.e. value **as mentioned in the NIT** in the form of demand draft in favour of UNIVERSITY OF CALCUTTA payable at Kolkata is to be attached with the tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenderers on application after issue of work order to the successful bidder. For successful tenderer the EMD will be returned on application after an equal amount of security deposit is deducted from the running bills.

Amount:-Rs

D.D No..... Dated / /20

Name of Issuing Bank:--

Branch :-

8. Work is to be carried out as per specification laid in the B.O.Q or PWD specification as per instruction of the University Engineer or his representative.



9. The materials brought to site for execution of the work should by no means be taken out of site without the permission of the Engineer C.U.
10. The rates must be quoted in words in figure other wise the tender will be cancelled.
11. The University will not be bound to accept the lowest bidder.
12. The University will not supply any materials to the contractor.
13. The contractor will work under the strict supervision of the Engineer/ Sub-Assistant Engineer. The estimate given along with the tender are provisional payment will be made on the actual work done jointly measured by the Engineer or his representative (Sub-Assistant Engineer) & the contractor or his representative. The contractor will have to submit bill in printed format in duplicate .
14. The contractor will have to take necessary instruction from the Engineer CU/ Sub-Assistant Engineer regarding the execution of work.
15. Defect & liability Period :- The defect & liability period will be for a period of six months from the date of completion of the job. Any defects pointed out during this period has to be mend good by the agency at their own cost failing which the retention money will be forfeited.

Sd/-

University Engineer

Name of the Agency:

Address :-

SIGNATURE OF THE CONTRACTOR WITH SEAL AND DATE

Specific price schedule for urgent plumbing and carpentry works in toilets of old hostel building at Carmichael Hall, 51, BaithakKhana Road, Kolkata -700 009

Rates according to P. W. D. Schedule 2017 (Effective From 01.11.2017)

Item	Description	Quantity	Rate	Amount (Rs.)
1	Supplying,fitting and fixing Low-down cistern parts - Rubber Kid (Page- 38 / Sl. No. 1iv)	12 Nos.	Rs. 304.00 Each.	3648.00
2	Supplying,fitting and fixing approved brand P.V.C. CONNECTOR white flexible, with both ends coupling with heavy brass C.P. nut, 15 mm dia. - 600 mm long (Page-43/Sl. No. 9iii)	6.00 nos.	Rs. 107.00 Each.	642.00
3	Supplying,fitting and fixing 32 mm dia. Flush Pipe of approved make with necessary fixing materials and clamps complete.- Polythene Flush Pipe (Page-81/Sl. No. 11i)	4 Nos.	Rs. 155.00 Each.	620.00
4	Supplying, fitting and fixing G.I. pipes of TATA make with all necessary accessories - 15 mm dia. medium quality. (Page-2/Sl. No. 1Aaii) 1.50 Mtr. X 4 nos = 6.00 Mtr.	6.00 Mtr.	Rs. 192.00 per Mtr.	1152.00
5	Supplying, fitting and fixing towel rail with two brackets. C.P. over brass - 25 mm dia. and 600 mm long (Page-82/Sl. No. 22aii)	5 Nos.	Rs. 430.00 Each.	2150.00
6	Supplying, fitting and fixing alloy iron with brass spindle bib cock/ stop cock of approved brand and make, spray painted and tested to 21 kg per sq. cm. - 15 mm (Page-6/Sl. No. 7gi) Bib Cock - 3, Stop Cock - 2	5 Nos.	Rs. 169.00 Each.	845.00
7	Supplying,fitting and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. - 1050 mm long (Page-43/Sl. No. 10iv)	5 Nos.	Rs. 91.00 Each.	455.00
8	Supplying, fitting and fixing Peet's valve fullway gunmetal standard pattern best quality of approved brand bearing I.S.I. marking with fittings (tested to 21 kg per sq. cm.). - 20 mm dia (Page-4/Sl. No. 4viii)	2 Nos.	Rs. 657.00 Each.	1314.00
9	Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark. - 100mm. X 58mm. X 1.90mm. (Page-140/Sl. No. 5vii)	30 Nos.	Rs. 47.00 Each.	1410.00
10	Anodisedaluminium barrel / tower / socket bolt (full covered) of approved manufactured from extruded section conforming to I.S. 204/74 fitted and fixed with cadmium plated screws: 150mm long x 12mm dia. bolt. (Page-144/Sl. No. 26v)	25 Nos.	Rs.88.00 Each.	2200.00
11	Anodisedaliminium D-type handle of approved quality manufactured from extruded section conforming to I.S. specification (I.S. 230/72) fitted and fixed complete: With continuous plate base (Hexagonal/ Round rod) - 100 mm grip x 12 mm dia rod. (Page-145/Sl. No.30aiii)	20 Nos.	Rs.85.00 Each.	1700.00
12	Plumbing Mistry (Page-113/Sl. No.1)	2 No.	Rs. 358.60 Each.	717.20
13	Plumbing Helper (Page-113/Sl. No.5)	2 No.	Rs. 297.00 Each.	594.00
Tentative Basic Cost =				Rs. 17,447.20
GST @ 12 % (this part to be checked by Office)			Rs.	2093.66
Cost of civil works excluding labour welfare cess			Rs.	19,540.86
Labour welfare cess @1%			Rs.	195.41
Cost of civil works including labour welfare cess - Total Cost			Rs.	19,736.27

Name Of The Agency:

Address Of The Agency:

Rate quoted by the Agency: (.....%)
Percent Below/ At Par/ Above



UNIVERSITY OF CALCUTTA
OFFICE OF THE UNIVERSITY ENGINEER
87/1 College Street
Darbhanga Building, Ground Floor
Kolkata-700073
Website :-www.caluniv.ac.in

NOTICE INVITING TENDER

University of Calcutta invites **sealed** tender from resourceful and bonafied contractors for the following work

1.	N.I.T. No	:	Eng /CT-291/19-20.	Dated 01/ 11 / 2019
2.	Name of Work	:	2 nd call for COST ESTIMATE FOR REPAIR AND RENOVATION WORK OF FIRST & SECOND FLOOR TOILETS OF P.G. LADY STUDENTS HALL AT 56& 58 M. G. ROAD, KOLKATA - 700 009	
3.	Estimated Cost put to Tender	:-	Rs358837.61	
4.	Earnest Money	:-	A sum of Rs17950/- (Rupees seventeen Thousand nine hundred and fifty only) in the form of CTS demand draft in favour of University of Calcutta payable at Kolkata is to be attached with the Tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenders on application after issuing of work order to the successful bidder. In case of successful tender the EMD will be returned on application after an equal amount of security deposit is deducted by the University from the running bills. EMD is exempted for those bidders who are registered with NSIC or any Government organization- to safeguard against a bidder withdrawing/altering his bid during the bid validity period.	
5.	Time of completion	:-	45 days	
6.	Eligibility Criteria	:-	Valid trade License , GST & Pan and credential for satisfactory completion of similar nature of job. Amounting 75 % of the estimated value in a single tender in the last three financial year . Government, Government Undertaking and University of Calcutta credentials are accepted.(only completion certificate of the work should be treated as Credential.	
7.	Last date of receipt of application for tender	:-	NA	
8.	Last date of Sale/ issue of tender papers		TO BE DOWNLOADED FROM WEBSITE.(www. caluniv.ac.in)	
9.	Last Date and Time of tender Submission	:-	13/11/2019.(up to 2.00 PM)	
10.	Date and Time of Tender Opening	:-	On or after 3:00 PM 13/11/2019	

N.I.T no ,Name of work and the date of opening should be written on the sealed envelope otherwise tender will not be opened thus cancelled.

The undersigned reserves the right to reject any or all Tenders without assigning any reason what so ever

UNIVERSITY ENGINEER (C.U)



UNIVERSITY OF CALCUTTA

Name of the work:-

2nd call for COST ESTIMATE FOR REPAIR AND RENOVATION WORK OF FIRST & SECOND FLOOR
TOILETS OF P.G. LADY STUDENTS HALL AT 56& 58 M. G. ROAD, KOLKATA - 700 009

N. I.T. no- Eng /CT-291/19-20. **Dated**01/ 11 / 2019

Estimated cost Put to Tender:-Rs358837.61

Name of Agency:-

Address of Agency:-

Rate quoted by Agency:- (%)
Percent Above / At par / Below

Signature of the Agency with date & stamp:-



UNIVERSITY OF CALCUTTA

N. I.T. no- Eng /CT-291/19-20. **Dated**01/ 11 / 2019

TENDER AND CONTRACT FOR WORK

GENERAL TERMS AND DIRECTION FOR THE GUIDANCE OF CONTRACT

1. Eligible Tenders will have to download the tender papers from the website & drop the filled tender papers signed with seal and date at every page along with copy of Valid Trade license's, GST & PAN and Credential for satisfactory completion of similar nature of job amounting to at least seventy five percent of the job value in a single tender from any Government, Govt. undertaking or University of Calcutta in the last three financial year in sealed envelope in the Tender box kept in the Office of the undersigned with in the specified time mentioned in the NIT. which will be opened by the undersigned or by his representative with in **the specified time and date mentioned in the NIT.** **The tendered must write the name of the work , NIT no , the date of opening and name of the bidder on the envelop failing which the tender will not be opened thus will be treated as cancelled.**
2. The rate should be quoted after inspection of the site and inclusive of all incidental charges i.e. freight, insurances, labour insurances, handling charges, necessary government taxes, duties etc as well as the Water, Electricity charges which are to be paid as per rules .
3. The contractor shall be responsible to ensure compliance with the provision of minimum wages act 1948 as modified up to date and the rules made in respect of any employees, employed by the contractor directly or through the petty or subcontractor for the purpose of carrying this contract. The contractor shall be responsible for any damage, injury or loss caused by the work or workmen to any person, animal or material during the progress of work.
4. Liquidated damage will be charged to the contractor if they fail to complete the work within the stipulated time, 0.01% per day to a maximum limit of 05 % of the contract value .



5. The allotted time for completion of the work is as specified in the NIT from the date of receipt of work order. Time is the essence of this contract. Normally no time extension will be granted. In case of prayer for extension of time the University authority has the full right reserved to grant it or discard it.

6. (a) If the successful contractor's bid rate is 80% or less than the estimated amount put to tender the contractor will have to submit a Bank Guarantee amounting to 10% of the Tendered amount before issue of Work order failing which the EMD will be forfeited and the agency may be blacklisted. The Bank Guarantee should be valid till the end of the contract period and shall be renewed accordingly if required. This bank Guarantee is an Additional Performance Security. So provision of deducting Security deposit from bills will hold goods per relevant clause of the contract. The bank Guarantee shall be returned immediately on successful completion of contract.

(b) The University authority will retain a sum amounting to 10% of the bill of the contract for a period of six months from the date of completion of work as **Security Deposit**. Which will be released after a period of six months from the date of completion of the work on application.

7. A sum of 5% of the estimated amount i.e. value **as mentioned in the NIT** in the form of demand draft in favour of UNIVERSITY OF CALCUTTA payable at Kolkata is to be attached with the tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenderers on application after issue of work order to the successful bidder. For successful tenderer the EMD will be returned on application after an equal amount of security deposit is deducted from the running bills.

Amount:-Rs

D.D No...... Dated / /20

Name of Issuing Bank:--

Branch :-

8. Work is to be carried out as per specification laid in the B.O.Q or PWD specification as per instruction of the University Engineer or his representative.



9.The materials brought to site for execution of the work should by no means be taken out of site without the permission of the Engineer C.U.

10. The rates must be quoted in words in figure other wise the tender will be cancelled.

11. The University will not be bound to accept the lowest bidder.

12.The University will not supply any materials to the contractor.

13. The contractor will work under the strict supervision of the Engineer/ Sub-Assistant Engineer. The estimate given along with the tender are provisional payment will be made on the actual work done jointly measured by the Engineer or his representative(Sub-Assistant Engineer)& the contractor or his representative. The contractor will have to submit bill in printed format in duplicate .

14. The contractor will have to take necessary instruction from the Engineer CU/ Sub-Assistant Engineer regarding the execution of work.

15.Defect & liability Period :-The defect & liability period will be for a period of six months from the date of completion of the job. Any defects pointed out during this period has to be mend good by the agency at their own cost failing which the retention money will be forfeited.

Sd/-

University Engineer

Name of the Agency:

Address :-

SIGNATURE OF THE CONTRACTOR WITH SEAL AND DATE

COST ESTIMATE FOR REPAIR AND RENOVATION WORK OF FIRST & SECOND FLOOR TOILETS OF P.G. LADY STUDENTS HALL AT 56& 58 M. G. ROAD, KOLKATA - 700 009 UNDER UNIVERSITY OF CALCUTTA

(The estimate based on 2017 P. W. D. Schedule & any non work schedule item rate will be follow the 2017 P. W. D.schedule and the item, quantity me be differ form the working schedule.)

P - 1 of

15

IT. No	Sch. Page No	DESCRIPTION OF WORK	NOS	QUANTITY	RATE	UNIT	AMOUNT Rs.	P
1	Page- 11 / Sl. No. 10	Stripping off worn out plaster and rking out joints of walls, celing etc. upto any height and in any floor including removing rubish and staking any where within the compound as directed.		192.14	19.00	Sqm	3650.66	
2	Page- 10 / Sl. No. 2	Dismantling all types of plain cement concrete works, stacking serviceable materials at site and reremoving rubbish as directed within a lead of 75 m In ground floor including roof. (a) upto 150 mm. thick			939.0	Cum	0	
		In first floor including roof. (a) upto 150 mm. thick			989.0	Cum	0	
3	Page-10 / Sl. No. 1	Dismantling all types of masonry excepting cement concrete plain of reinforced, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m. a) In ground floor including roof.			437.0	Cum	0	
4	Page- 11 / Sl. No. 6	Dismantling artificial stone flooring upto 50 mm. thick by carefully chiselling without damaging the base and removing rubbish as directed within a lead of 75 m. In ground floor including roof. In first floor including roof. In 2nd floor including roof.						
					50.00	Sqm		
				14.34	56.00	Sqm	803.04	
				14.34	62.00	Sqm	889.08	
5	Page- 12 / Sl. No. 11	Cutting chase upto 125 x 150 mm. and subsequent						

mending of damages.

(a) in brick wall [Cement-3.6
Kg/Mtr]

53.12 93.00 Mtr. 4940.16

P - 2 of
15

IT No	Sch. Page No	DESCRIPTION OF WORK	NO S	QUANTIT Y	RATE	UNI T	AMOUNT Rs. P
6	Page- 24 / Sl. No. 4	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement,if any, in ground floor as per relevant IS codes. a) Pakur Variety In First floor . a) Pakur Variety In 2nd floor . a) Pakur Variety					
					3886	Cum	
			1.00		3981	Cum	3981.00
			1.00		4076	Cum	4076.00
7	Page- 189 / Sl. No. 1	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints or roughening of concrete surface, including throating, nosing and drip course where necessary (ground floor) (i) With 6:1 cement mortar (b) 20 mm. thick plaster (a) 25 mm. thick plaster (ii) With 4:1 cement mortar (c) 10 mm. thick plaster In Firsr floor (i) With 6:1 cement mortar (a) 25 mm. thick plaster					
					167.0	Sqm	
					0		
					195.0	Sqm	
					0		
					129.0	Sqm	
					0		
					199.0	Sqm	16264.27
			81.73		0		

		(b) 20 mm. thick plaster		171.0	Sqm	0	
		(ii) With 4:1 cement mortar (c) 10 mm. thick plaster	14.34	133.0	Sqm	0	1907.22
		In second floor					
		(i) With 6:1 cement mortar (a) 25 mm. thick plaster	81.73	203.0	Sqm	0	16591.19
		(b) 20 mm. thick plaster		175.0	Sqm	0	
		(ii) With 4:1 cement mortar (c) 10 mm. thick plaster	14.34	137.0	Sqm	0	1964.58
8	Page- 192 / Sl. No. 15	Neat cement punning about 1.5 mm. thick in wall, dado, window, sills, floor, drain etc.	6	34.00	Sqm		204

P - 3 of
15

IT . No	Sch. Page No	DESCRIPTION OF WORK	NO S	QUANTIT Y	RATE	UNI T	AMOUNT Rs. P
9	Page- 64/ Sl. No. 35	Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc. (A) Floor With Sand Cement Mortar (1:4) 20 mm thick					

& 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m& joint filling using white cement slurry @ 0.20kg/Sq.m.
(a) Area of each tile upto 0.09 Sq.m

(i) Coloured decorative		746.0	Sqm	
		0		
In first floor		751.0	Sqm	10769.34
	14.34	0		
In second floor		756.0	Sqm	10841.04
	14.34	0		

(B) Wall
With Sand Cement Mortar (1:3) 15 mm thick
& 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m& joint filling using white cement slurry @ 0.20kg/Sq.m.
(a) Area of each tile upto 0.09 Sq.m

(i) Coloured decorative		749.0	Sqm	
		0		
In first floor		754.0	Sqm	37111.88
	49.22	0		
In second floor		759.0	Sqm	37357.98
	49.22	0		

IT . No	Sch. Page No	DESCRIPTION OF WORK	NO S	QUANTIT Y	RATE	UNI T	AMOUNT Rs. P
10	Page - 195 / It -7	Applying Interior grade Acrylic Primer of approved quality and brand					

on plastered or concrete surface old or new surface to receive

		Distemper/ Acrylic emulsion paint including scraping and preparing the surface throughly, complete as per manufacturer's specification and as per direction of the EIC. (In Ground Floor)				
		(a) One Coat				
		i) Water based interior grade Acrylic Primer		30.80	Sq.M	
		In first floor	100.48	30.80	Sq.M	3094.78
		In second floor	100.48	30.80	Sq.M	3094.78
11	Page - 196 / It -11	Synthetic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothning of surface. Two Coats		68.00	Sq.M	
		In first floor	100.48	68.00	Sq.M	6832.64
		In second floor	100.48	68.00	Sq.M	6832.64
12	Page - 200 / It - 1	(b) Priming one coat on timber of plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	28.78	38.00	Sq.M	1093.64
		(a) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	12.16	29.00	Sq.M	352.64

IT No	Sch. Page No	DESCRIPTION OF WORK	NO S	QUANTIT Y	RATE	UNI T	AMOUNT Rs. P
13	Page - 200 / It - 2	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : (a) On timber or plastered surface : With super gloss (hi-gloss) - [iv] Two coats (with any shade except white)		28.78	81.00	Sq.M	2331.18
		b) On steel or other metal surface: With super gloss (hi-gloss) (iv) Two coats (with any shade except white)		12.16	79.00	Sq.M	960.64
14	Page - 116 / It - 5	Supplying, Fitting & Fixing Factory made prelaminated P.V.C. door frame of size 50 mmx47 mm with a wall thickness of 5 mm, made out of extruded 5 mm Prelaminated PVC sheet miter cut at two corners and joined with two nos of 1.5 mm long brackets of 15 mm x15 mm M.S. square tube. The two vertical door profiles are to be reinforced with 19 mmx 19 mm M.S. Square tube of 19 gauge, weather seal to be provided through out the frame. The door frame shall be fixed with the wall using 65/100 mm M.S. Screws through the frame by using P.V.C fasteners. A minimum of 4 Nos of screws to be provided for each vertical member and minimum 2 Nos for horizontal member etc. complete as per Manufacturer's		41	385	Mtr.	15785

- 15 Page - 125 / It - 14
 specification and direction of Engineer-in-Charge.
 Supplying, fitting & fixing fibre reinforced polymer (FRP) Composite door
 shutters as per approved design with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolithic composite structure as per approved technology of Department of Science and Technology (DST) to

P - 6
 of 15

IT No	Sch. Page No	DESCRIPTION OF WORK	NO S	QUANTIT Y	RATE	UNI T	AMOUNT Rs. P
		satisfy IS:4020 door testing performance criteria. In ground floor. (i) 32 mm thick			2763	Sq. m	
		In first floor. (I) 32 mm thick		1.62	2777	Sq. m	4498.74
		In 2nd floor. (I) 32 mm thick		1.62	2791	Sq. m	4521.42
16	Page - 128 / It - 18	18 Supplying, Fitting & Fixing 30 mm thick thick both side prelaminated Double Leaf Factory made solid Panel PVC Door Shutter consisting of outer frame made out of M.S. tubes of 19 gauge thickness and size 19 mmx19 mm for styles, top and bottom rails, M.S. frame shall have cost of steel primers of approved make and manufacture, M.S. frame covered with 5 mm th. heat moulded PVC "C" channel of size 30 mm th, 70 mm width out of which 50 mm shall be flat and 20 mm shall					

be tapered in 45 degree angle on either sides forming styles; and 5 mm th. 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm tapered in 45 degree on the inner side to form top & bottom rail and 115 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided either side of the panel with 10 mm (5 mmx2) th.,20 mm wide cross PVC sheet as gap insert for top rail and bottom rail. Paneling of 5 mm th. both side PVC sheet to be fitted in the M.S. frame welded/sealed to the styles & rails with 7 mm (5 mm+2 mm) th.x15 mm wide PVC sheet beading on inner side and joined together with solvent cement adhesive. An additional 5 mm th. PVC strip of 20 mm which is to be stuck on the interior side of the "C" channel using PVC solvent adhesive etc. complete excluding all necessary hardwares as per direction of Engineer-in-Charge.

P - 7 of
15

IT No	Sch. Page No	DESCRIPTION OF WORK	NO S	QUANTIT Y	RATE	UNI T	AMOUNT Rs. P
		In ground floor.			2714	Sq. m	
		In first floor. (I) 32 mm thick		6.5	2728	Sq. m	17732
		In 2nd floor. (I) 32 mm thick		6.5	2742	Sq. m	17823

17	Page- 140 / Sl. No.4	Supplying, fitting and fixing M.S. clamps for door and window frame made of flat bent bar, end bifurcated with necessary screws etc. by cement concrete(1:2:4) as per direction. (Cost of concrete will be paid separately) (c) 40mm X 6mm, 125mm Length 4x6x2=48	48	20.00	Each	960.00
18	Page- 140 / Sl. No.5	Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark (iv) 75mm. X 47mm. X 1.70mm. 4x6x2=48	48	40.30	Each	1934.40
19	Page- 143/ Sl. No.24	(A) Iron door ring of approved quality fitted and fixed with nut and washer complete. (i) 50mm dia. 2x4x2=16	16	17.00	Each	272.00
20	Page- 99/ Sl. No.61	Anodisedaluminium barrel / tower / socket bolt (full covered) of approved manufactured from extruded section conforming to I.S.204/74 fitted & fixed with cadmium plated. (iv) 150mm long x 10mm dia. bolt. 2x4x2=16	16	63.00	Each	1008.00
21	Page- 152/Sl.No.3 0	Labour for taking out door and window frame including shutter for repair or	16.24	119.0 0	Sq. m	1932.56

IT . N o	Sch. No	Page No	DESCRIPTION OF WORK	NO S	QUANTIT Y	RATE	UNI T	AMOUNT Rs. P
-------------------	------------	------------	---------------------	---------	--------------	------	----------	--------------------

replacement of different parts of the frame &refixing the same including mending good all damaes complete. (Concrete and brick work for mending damage will be paid separately)
(a) Upto area 2.5 Sq.m

22	Page-152/SI.No.3 1	<p>Taking out shutter of door and window, dismantling by parts (for repair or replacement of damaged parts) , reassembling and refitting and rehangng same with old fittings but with new screws as necessary. (Where different parts of same shutter are renewed under different item, payment under item 73 will be made once only). 1st floor- W- 1x0.9x1.20=1.08, 1x0.5x0.90=0.45, 1x0.90x1.30 = 1.17 2nd floor- W- 1x0.9x1.20=1.08, 1x0.5x0.90=0.45, 1x0.90x1.30 = 1.17</p>	5.4	126.0 0	Sq. m	680.4
23	Page-153/SI.No.3 9	<p>Styles and rails of wooden shutters fitted and fixed complete. (Payment to be made on area of new work only). In Ground Floor: (ii) 35mm Thick shutter. (b) Sishu, Gamar, Champ,Badam,Bhola, Mogra, Hallak. In 1st floor. 3x0.9x0.10=0.27, 2x1.20x0.10=0.24, 3x1.30x0.1=0.39 In 2nd floor. 3x0.9x0.10=0.27, 2x1.20x0.10=0.24, 3x1.30x0.1=0.39</p>	1.8	2292	Sq. M	4125.6
24	Page-3/SI.No.3	<p>Supplying, fitting and fixing shower of approved brand and make. (iii) Chromium plated shower arm 240 mm long (Equivalent to Code</p>	4	309	Each	1236

No.

536(A) & Model - Tropical /
Sumthing Special of ESSCO or
similar
brand).

P - 9 of
15

IT . N o	Sch. Page No	DESCRIPTION OF WORK	NO S	QUANTIT Y	RATE	UNI T	AMOUNT Rs. P
25	Page- 6/Sl.No.7	Supplying, fitting and fixing bib cock or stop cock. (a) (i) Chromium plated Bib Cock short body (Equivalent to Code No. 511 & Model - Tropical / Sumthing Special of ESSCO or similar brand).		8	539	Each	4312
26	Page- 67 /Sl. No. 18	Supplying, fitting and fixing C.I. round grating (ii) 150 mm		4	64.00	each	256
27	Page- 76 /Sl. No. 1	Dismantling H.C.I. pipe with fittings including melting lead caulked joints (iii) 100 mm 4x3.90=15.60		15.6	64.00	metr e	998.4
28	Page-79 / Sl. No. 4	Supplying, fitting and fixing Orissa pattern water closet in white glazed vitreous chinaware of approved make in position complete excluding 'P' or 'S' trap (excluding cost of concrete for fixing). (i) 580 mm X 440 mm		4	1613	each	6452.00
29	Page-80 / Sl. No. 7	Supplying, fitting and fixing Squating plate with integral flushing in white					

vitreous chinaware of approved make in cement concrete (6:3:1) with jhama chips complete. (Payment of concrete will be paid seperately).
(i) 450 mm X 350 mm

4 881 each 3524.00

30 Page-80 /
Sl. No. 8

Supplying, fitting and fixing Half round channel with or without outlet as

required set in cement concrete (6:3:1) with jhama chips complete.

P - 10 of
15

IT No	Sch. Page No	DESCRIPTION OF WORK	NO S	QUANTIT Y	RATE	UNI T	AMOUNT Rs. P
		(Payment of concrete will be paid seperately). (i) 600 mm X 100 mm b) White vitreous chinaware 4x1.20=4.80		4.8	579	each	2779.20
31	Page-81/ Sl. No.11	Supplying,fitting and fixing 32 mm dia. Flush Pipe of approved make with necessary fixing materials and clamps complete.		4	155	each	620.00
32	Page-81/ Sl. No.15	i) Polythene Flush Pipe Supplying, fitting and fixing bevelled edged mirror 5.5 mm thick silver red as per I.S. 3438 / 1965 together with brass C.P. hinges. (i) 450 mm X 300 mm		4	367	each	1468.00
33	Page-6 / Sl. No. 7	Supplying, fitting and fixing bib cock or stop cock. (g) Supplying, fitting and fixing alloy iron with brass spindle bib cock/ stop cock of approved brand and make, spray painted and tested to 21 kg per					

sq. cm.
(i) 15 mm

6 169 each

34 Page- 2 /
Sl. No. 1

Supplying, fitting and fixing G.I. pipes of TATA make with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, longscrew, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials and two coats of painting with approved paint in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accesories, specials. Payment for painting will

P - 11 of
15

IT . No	Sch. Page No	DESCRIPTION OF WORK	NO S	QUANTIT Y	RATE	UNI T	AMOUNT Rs. P
		be made seperately)					
		(A) For Exposed Work					
		a) (ii) 15 mm dia. medium quality		48	192	Mtr	9216.00
		b) (ii) 20 mm dia. medium quality		12	226	Mtr	2712.00
35	Page- 65 / Sl. No. 14	Supplying,fitting and fixing cast iron 'P' or 'S' trap conforming to I.S. 3989 / 1970 and 1729 / 1964 including lead caulked joints and painting two coats to the exposed surface. (Painting to be paid seperately). (A) 'S' Trap (iii) 100 mm		4	803	each	3212.00
36	Page-65 / Sl. No. 15	Supplying, fitting and fixing cast iron extension pipes for using in Traps only					

(connector) conforming to
I.S.3989/1970 and 1729/1964
including lead
caulked joints complete and
painting two coats to the exposed
surface

(a) (i) 100 mm X 150 mm

4 461 each 1844.00

37 Page-82 /
Sl. No. 18 Supplying, fitting and fixing soap
holder.

(a) PTMT (Prayag or equivalent)

4 135 each 540.00

38 Page- 85 /
Sl. No. 2 Dismantling Indian W.C. including
taking out base concrete as
necessary.

4 45 each 180.00

39 Page-82 /
Sl. No. 22 Supplying, fitting and fixing towel
rail with two brackets.

(a) C.P. over brass

(ii) 25 mm dia. and 600 mm long

4 430 each 1720

P - 12 of
15

IT No	Sch. Page No	DESCRIPTION OF WORK	NO S	QUANTIT Y	RATE	UNI T	AMOUNT Rs. P
40	Page- 36 / Sl. No. 2	Supplying, fitting and fixing 10 litre P.V.C. low-down cistern conforming to I.S. specification with P.V.C. fittings complete, C.I. brackets including two coats of painting to bracket etc.	4	1015	each	4060.00	
41	Page- 77 / Sl. No.12	Removing chokage of H.C.I. or S.W. pipe with split bamboo. (a) Underground		11	metr e		

		b) Over ground	23.4	9	metre	210.6
42	Page- 1 / Sl. No.1	<p>Supplying, fitting & fixing Cast iron soil pipe only conforming to I.S. 3989/</p> <p>2009 and I.S. 1729/2002 with bobbins, nails etc. including making holes in the wall, floor etc. and cutting trenches etc. in any floor through masonry concrete, if necessary, and mending good damages with necessary jointing materials and painting two coats to the exposed surface with approved paint complete. (Measurement will be made along the center line of the total pipe line in fitted condition including specials, payment for specials & Painting will however be paid seperately).</p> <p>(a) With valamoid joints including sealing with sand cement mortar (4:1) upto quarter depth.</p> <p>(ii) 100 mm dia. (internal)</p>				
		3.0x7 = 21.0,	21	688	metre	14448
43	Page- 233 / Sl. No.1	<p>Supplying profiles of required section made of Aluminium Alloy</p> <p>Extrusions conforming to IS: 732-1983 and IS: 1285- 1975; Anodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composit door, sliding &</p>				

IT . N o	Sch. Page No	DESCRIPTION OF WORK	NO S	QUANTIT Y	RATE	UNI T	AMOUNT Rs. P
		casement windows, partitions, formed of basic sections of any ISI embossed / certified make and brand as per direction of Engineer - In-Charge. (Payment will be made on finished length of the work). (A) In 10-12 Micron thickness Annodizing film I) Natural white a) 2- track sliding window i) Bottom frame ii) Top and side frame. d) Shutter for all track sliding window. i) Bottom & Top member. ii) Style side member. iii) Interlock member.					
				2.95	218	Mtre.	643.1
				10.07	195	Mtre.	1963.65
				6.5	117	Mtre.	760.5
				3.56	119	Mtre.	423.64
				3.56	148	Mtre.	526.88
44	Page- 239 / Sl. No.2	Labour charge for fabrication and installation of composite door, window, partitions made from annodized extruded alloy aluminium sections for the following units:- (A) Glazed aluminium sliding windows made of extruded and annodized alloy aluminium sections, fabrications, including cutting to proper shape and size, drilling and aligning of window shutter frame fitted with in built locking arrangements, sliding rollers and other necessary fittings, fixture, adhesives and joineries along with extruded neoprine or EPDM gasketing in between window frame and masonry work (walls, column,					

beam.lintels etc.) as well as between glass and shutter frame for fixing glass and Polysulphide sealant and in between shutter and window frame where necessary including cutting to requisite size and fixing glass as per drawing, specification and direction of EIC.
The rate includes the hire charge of all tools and plants, including all

P - 14 of
15

IT No	Sch. Page No	DESCRIPTION OF WORK	NO S	QUANTIT Y	RATE	UNI T	AMOUNT Rs. P
		incidental charges, adhesive, joineries such as screw, cleat angle etc. but excluding the cost of extruded aluminium sections, glass, neoprene / EPDM gasket, locking arrangement and rollers.					
		i) 2 track sliding window. W-1.30x1.53=1.99, 0.75x0.83=0.62, 0.90x1.20= 1.08		3.69	696	Sq.M	2568.24
45	Page- 242 / Sl. No.8	Supplying EPDM gasket of approved make and brand as per direction of Engineer in charge. i) For sliding windows a) ' T' shaped EPDM gasket for frames.		20.26	13	Mtre.	263.38
46	Page- 242 / Sl. No 7	Supplying maruti lock (100mm)		3	46	Pair	138
47	Page- 243 / Sl. No 9	Supplying bubble free float glass of approved make and brand					

conforming to IS: 2835-1987.

		ii) 4mm thick coloured / tinted / smoke glass. W= 1.30x1.53=1.99, 0.75x0.83=0.62,0.90x1.20=1.08	3.69	468	Sq.M	1726.92
48	Page-13 / Sl. No. 12	Removal of rubbish,earth etc. from the working site and disposal of the same beyond the compound, in conformity with the Municipal / Corporation Rules for such disposal, loading into truck and cleaning the site in all respect as per direction of Engineer in charge	7.22	166.0 0	Cum	1198.52
		192.14x0.025=4.80, 2x14.34x0.05=1.43, 53.12x0.125x0.15=0.99 Add @ 12 % for GST charge			Total Rs.- Rs.	317218.54 38066.22 <u>355284.76</u>
		Add @ 1 % forlabour welfare cess.			Rs.	<u>3552.85</u>
			Grand Total	Rs. -		<u>358837.61</u>

P - 15 of
15

IT . N o	Sch. Page No	DESCRIPTION OF WORK	NO S	QUANTIT Y	RATE	UNI T	AMOUNT Rs. P
-------------------	-----------------	---------------------	---------	--------------	------	----------	--------------------

(Rupees three lakh fifty eight thousand eight hundred thirty seven and sixty one Paise Only)

Name of the Agency -

Address of the Agency -

Rate quoted by the Agency -

Signature of the Agency with date -



UNIVERSITY OF CALCUTTA
OFFICE OF THE UNIVERSITY ENGINEER
87/1 College Street
Darbhanga Building, GroundFloor
Kolkata-700073
Website :-www.caluniv.ac.in

NOTICE INVITING TENDER

University of Calcutta invites **sealed** tender from resourceful and bonafied contractors for the following work

1.	N.I.Q. No	:	Eng /CQ-292/19-20. Dated 01/ 11/ 2019
2.	Name of Work	:	2 nd call for Supply and installation of new ISI mark ABC type fire extinguishers on buy back of the old expired/damaged ones at P.G.lady Student hall at- 56&58M.G.Road Kol-09& 24& P.G.MEN Student hall at 7, waliullah lane Kolkata-16 and at Goenka Hospital,148, Muktarambabu Street under, University of Calcutta.
3.	Estimated Cost put to Tender	:-	Rs NA
4.	Earnest Money	:-	A sum of 5% of the Quoted amount in the form of CTS demand draft in favour of University of Calcutta payable at Kolkata is to be attached with the Tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenders on application after issuing of work order to the successful bidder. In case of successful tender the EMD will be returned on application after an equal amount of security deposit is deducted by the University from the running bills. EMD is exempted for those bidders who are registered with NSIC or any Government organization- to safeguard against a bidder withdrawing/altering his bid during the bid validity period.
5.	Time of completion	:-	45days
6.	Eligibility Criteria	:-	Valid trade License , GST & Pan and credential for satisfactory completion of similar nature of job. Amounting 75 % of the estimated value in a single tender in the last three financial year . Government, Government Undertaking and University of Calcutta credentials are accepted.(only completion certificate of the work should be treated as Credential.
7.	Last date of receipt of application for tender	:-	NA
8.	Last date of Sale/ issue of tender papers		TO BE DOWNLOADED FROM WEBSITE.(www. caluniv.ac.in)
9.	Last Date and Time of tender Submission	:-	13/11/2019.(up to 2.00 PM)
10.	Date and Time of Tender Opening	:-	On or after 3:00 PM 13/11/2019

N.I.Qno ,Name of work and the date of opening should be written on the sealed envelope otherwise tender will not be opened thus cancelled.

The undersigned reserves the right to reject any or all Tenders without assigning any reason what so ever.

UNIVERSITY ENGINEER (C.U)



UNIVERSITY OF CALCUTTA

Name of the work:- 2nd call for Supply and installation of new ISI mark ABC type fire extinguishers on buy back of the old expired/damaged ones at P.G.lady Student hall at- 56&58 M.G.Road Kol-09 & 24& P.G.MEN Student hall at 7, waliullah lane Kolkata-16 and at Goenka Hospital,148, Muktarambabu Street under, University of Calcutta.

N. I.Q. no- Eng /CQ-292/19-20. **Dated**01/ 11/ 2019

Name of Agency:-

Address of Agency:-

Rate quoted by Agency:- (%)
Percent Above / At par / Below

Signature of the Agency with date & stamp:-



UNIVERSITY OF CALCUTTA

N. I.Q. no- Eng /CQ-292/19-20. Dated 01/ 11/ 2019

TENDER AND CONTRACT FOR WORK

GENERAL TERMS AND DIRECTION FOR THE GUIDANCE OF CONTRACT

1. Eligible Tenders will have to download the tender papers from the website & drop the filled tender papers signed with seal and date at every page along with copy of Valid Trade license's, GST & PAN and Credential for satisfactory completion of similar nature of job amounting to at least seventy five percent of the job value in a single tender from any Government, Govt. undertaking or University of Calcutta in the last three financial year in sealed envelope in the Tender box kept in the Office of the undersigned with in the specified time mentioned in the NIQ. which will be opened by the undersigned or by his representative with in **the specified time and date mentioned in the NIQ.** **The tendered must write the name of the work ,NIQ no , the date of opening and name of the bidder on the envelop failing which the tender will not be opened thus will be treated as cancelled.**
2. The rate should be quoted after inspection of the site and inclusive of all incidental charges i.e. freight, insurances, labour insurances, handling charges, necessary government taxes, duties etc as well as the Water, Electricity charges which are to be paid as per rules .
3. The contractor shall be responsible to ensure compliance with the provision of minimum wages act 1948 as modified up to date and the rules made in respect of any employees, employed by the contractor directly or through the petty or subcontractor for the purpose of carrying this contract. The contractor shall be responsible for any damage, injury or loss caused by the work or workmen to any person, animal or material during the progress of work.
4. Liquidated damage will be charged to the contractor if they fail to complete the work within the stipulated time, 0.01% per day to a maximum limit of 05 % of the contract value .



5. The allotted time for completion of the work is as specified in the NIQ from the date of receipt of work order. Time is the essence of this contract. Normally no time extension will be granted. In case of prayer for extension of time the University authority has the full right reserved to grant it or discard it.

6. (a) If the successful contractor's bid rate is 80% or less than the estimated amount put to tender the contractor will have to submit a Bank Guarantee amounting to 10% of the Tendered amount before issue of Work order failing which the EMD will be forfeited and the agency may be blacklisted. The Bank Guarantee should be valid till the end of the contract period and shall be renewed accordingly if required. This bank Guarantee is an Additional Performance Security. So provision of deducting Security deposit from bills will hold goods per relevant clause of the contract. The bank Gurrantee shall be returned immediately on successful completion of contract.

(b) The University authority will retain a sum amounting to 10% of the bill of the contract for a period of six months from the date of completion of work as **Security Deposit**. Which will be released after a period of six months from the date of completion of the work on application.

7. A sum of 5% of the estimated amount i.e. value **as mentioned in the NIQ** in the form of demand draft in favour of UNIVERSITY OF CALCUTTA payable at Kolkata is to be attached with the tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenderers on application after issue of work order to the successful bidder. For successful tenderer the EMD will be returned on application after an equal amount of security deposit is deducted from the running bills.

Amount:-Rs

D.D No..... Dated / /20

Name of Issuing Bank:--

B ranch :-

8. Work is to be carried out as per specification laid in the B.O.Q or PWD specification as per instruction of the University Engineer or his representative.



9.The materials brought to site for execution of the work should by no means be taken out of site without the permission of the Engineer C.U.

10. The rates must be quoted in words in figure other wise the tender will be cancelled.

11. The University will not be bound to accept the lowest bidder.

12.The University will not supply any materials to the contractor.

13. The contractor will work under the strict supervision of the Engineer/ Sub-Assistant Engineer. The estimate given along with the tender are provisional payment will be made on the actual work done jointly measured by the Engineer or his representative(Sub-Assistant Engineer)& the contractor or his representative. The contractor will have to submit bill in printed format in duplicate .

14. The contractor will have to take necessary instruction from the Engineer CU/ Sub-Assistant Engineer regarding the execution of work.

15.Defect & liability Period :-The defect & liability period will be for a period of six months from the date of completion of the job. Any defects pointed out during this period has to be mend good by the agency at their own cost failing which the retention money will be forfeited.

Sd/-

University Engineer

Name of the Agency:

Address :-

SIGNATURE OF THE CONTRACTOR WITH SEAL AND DATE

Name of work:-2nd call for Supply and installation of new ISI mark ABC type fire extinguishers on buy back of the old expired/damaged ones at P.G.lady Student hall at- 56&58 M.G.Road Kol-09 & 24& P.G.MEN Student hall at 7, waliullah lane Kolkata-16 and at Goenka Hospital,148, Muktarambabu Street under, University of Calcutta.

Sl.no	Description of Work	UNIQ	Quantity	Rate	Amount
1	Supply and installation of new ISI mark ABC type fire extinguishers on buy back of the old expired/damaged ones at P.G.lady Student hall at- 56&58 M.G.Road Kol-09 & 24& P.G.MEN Student hall at 7, waliullah lane Kolkata-16 and at Goenka Hospital,148, Muktarambabu Street under, University of Calcutta..	each	60		
2	Buy back price of the existing the damaged /expired fire extinguisher cylinders at the above mentioned sites(agency must visit the sites before quoting)	each	40		
	Total Cost inclusive all taxes				

Name and Address of the Agency:-

Rate Quoted :- (in figure)-

(In words):-

Signature of the Agency with date and seal:-